

CoRTeC: Cohort-Conditioned Differentially Private Synthetic Tabular Data from a Frozen Language Model

Calister Nnona

calisternnona@gmail.com

DOI: [10.5281/zenodo.22945315](https://doi.org/10.5281/zenodo.22945315)

Abstract. Differentially private synthetic tabular data is worth producing only if a model trained on it performs as one trained on the real records. The deployed marginal mechanisms, MST and AIM, were built for marginal workloads and are evaluated on them; measured instead on this quantity, at library defaults and $\epsilon = 2$ on UCI Adult, their output trains models 0.14 to 0.17 AUC below a same-size real sample. CoRTeC spends the privacy budget once, on a release built for a downstream model, and trains nothing. Within publicly defined cohorts it publishes one Laplace histogram per attribute and outcome class, and a table of target rates over disjoint cells, so conditional structure costs one query per level. A frozen language model then decodes the release under exact per-bin counts and selection from a pool. It never sees a private record, so generation is post-processing: unlimited datasets at no further privacy cost. At $\epsilon = 2$ and $n = 300$, no model trained on CoRTeC's output separates from one trained on a real sample of the same size on census or credit data, one tree model is 0.05 AUC short on clinical data, and 1-way marginal error is within 0.005 of MST's on the first two and below it on the third. The gap lies largely in what is released: giving MST and AIM a private conditional table recovers most of it at no change to either mechanism. Four membership-inference attacks validated on a positive control reach at most 0.049 advantage against a permitted 0.762. Both criteria the field selects synthesisers on are saturated: real data with its target permuted passes a 90% marginal-similarity bar, and a language model given only column names passes aggregate downstream utility on a public benchmark. Only conditional and subgroup measures, against a real-sample and a no-information floor, separate a mechanism that transmits the institution's structure from one that recites a prior.

1. Introduction

An institution that holds sensitive tabular data usually wants three things its obligations forbid. It wants to train a model outside its own perimeter; to give a realistic sample to a partner or a vendor; and to let researchers work on the problem without working on the people. Synthetic data with a differential privacy guarantee [13, 14] is the accepted way to do all three. Whether it is worth doing depends on one question: if I train on the synthetic data instead of the real data, how much accuracy do I lose?

The mechanisms an institution can deploy today do not answer that question in their own papers. The marginal-based synthesisers MST [28] and AIM [29] are evaluated on marginal workload error, the error in the distributions of single columns and of small groups of columns. They attain low error on that measure, and they were built for published tables and contingency reports rather than for training models.

The generative models trained under differential privacy [24, 38, 49] are evaluated on downstream utility, the accuracy of a model trained on the synthetic data and tested on real data. On Adult at $\epsilon = 2$ they do not preserve the target's base rate.

The methods that do reach real-data utility fine-tune a language model on the records [5, 45]. They either carry no privacy guarantee or train on the private data under DP-SGD [1], gradient descent with clipped and noised updates. DP-SGD is expensive, and it places the private data on the training hardware. PATE [35, 36], an ensemble of teachers trained on disjoint shards of the private data whose noised votes label a public dataset, would avoid that. But it needs a public transfer set drawn from roughly the same distribution as the private data, and where privacy matters most, in a hospital's encounter records or a bank's default history, no such set exists.

A practitioner therefore chooses between two options. One is a mechanism that optimises low-order marginals rather than the structure a downstream model needs. The other is a large language model asked to invent plausible records. That is fast and needs no privacy accounting, but the model knows nothing about the institution's data.

CoRTeC. CoRTeC separates two things every other method does together: spending the privacy budget and producing records. First it spends the budget, once, on a statistics release. The release contains:

- cohorts (groups of records) formed by a public stratification rule, meaning bands of one or two attributes fixed before the data is seen;

- one differentially private histogram per attribute and per outcome class inside each cohort;
- a private class balance (the share of each outcome) and a private cohort size; and
- a private table of target rates over the cells of a conditional hierarchy, meaning nested subgroups defined by one, two or three attributes, each subgroup being a cell.

Then a frozen, un-finetuned language model reads that release, and nothing else, and writes records that match it. Each batch is told the exact number of rows it must produce per bin, per category and per outcome. From a pool of generated rows, the pipeline keeps the rows whose cell counts match the release. Wherever the release describes the class shape at bin resolution, the kept values are redrawn inside their released bins.

This design has four consequences, and they are the reasons to use it.

The privacy argument is small. The generator never sees a private record, so its work is post-processing of a differentially private release: a computation on the release alone, which adds no privacy cost. The privacy analysis therefore reduces to the release, which is a composition of counting queries.

Generation costs no privacy and can run anywhere. Any number of datasets can be drawn from one release at no further privacy cost, and the model can be a tenant-isolated enterprise endpoint or an air-gapped local model with the same guarantee.

The budget goes to the structure a classifier needs, and it goes there cheaply. A downstream model needs the conditional structure and the per-class shape of each attribute. Histograms have sensitivity 1 regardless of resolution, and disjoint cohorts and cells compose in parallel, so the release carries that structure at $6.7\times$ more budget per statistic than the moment-based implementation this method replaced: private clustering for cohorts, a mean and a standard deviation per attribute, and basic composition across cohorts (Section 4.8).

No statistician is needed. An auto-configurator chooses the cohorts and the hierarchy from the schema and the budget.

What we find. We test at $\epsilon = 2$, where ϵ is the privacy budget and smaller is stronger, and at $n = 300$, on three datasets: census, finance, and a national health examination survey.

On fidelity, CoRTeC's 1-way marginal error, the error in each single column's distribution, is within 0.005 of MST's on Adult and finance, and below it on NHANES. It is below the error of a real sample of the same size, and below AIM's, on every dataset. Its 2-way error, over pairs of columns, is below both marginal methods' on every dataset.

On utility, no student separates from the real-sample floor on Adult or finance at three draws each, and the powered six-draw test is Adult's, on the earlier release; on NHANES the random forest is 0.049 short ($p = 0.033$ before correction), gradient boosting 0.036 ($p = 0.10$) and logistic regression 0.035 ($p = 0.32$). The floor is the accuracy of a model trained on a real sample of the same size. The linear model is above it on Adult and within 0.006 of it on finance. Measured on this deliverable, models trained on AIM's and MST's output at library defaults score 0.02 to 0.18 lower in AUC, the area under the ROC curve, which is the utility measure used throughout. Of 35 comparisons against AIM and MST on Adult and finance, corrected for multiple testing with Holm's procedure, 29 favour CoRTeC, none favours a baseline, and six do not separate. AIM keeps the lowest error on its own 3-way workloads, sets of three-column marginals, at adequate sample size, which its design predicts.

Two results corrected our own framing. A private relationship forced into the data survives MST essentially perfectly (slope 0.998 on Diabetes 130, 0.946 on NHANES), so the marginal methods' utility gap is not an inability to carry conditional structure: on NHANES, the one dataset with both measurements, MST carries the forced rate and still trains the random-forest student 0.082 AUC below a real sample's. On Adult their loss is measurable instead as a 2.2 to $2.8\times$ inflation of pairwise feature dependence relative to real data of the same size; CoRTeC inflates it by $1.24\times$.

The second result is that CoRTeC's own conditional fidelity, how closely the outcome rate within each subgroup matches the private data, is decided by whether reasoning is enabled in the generator, the model's option to think through a request before answering. That single flag changes conditional error by a factor of 3.8, and downstream AUC does not detect the change. This finding has a methodological consequence, developed in Section 6.3: both criteria the field selects synthesisers on, marginal similarity and aggregate downstream utility, are saturated. A known-useless dataset passes the first, and on a public benchmark an ungrounded language model passes the second.

Contributions. In summary, this paper makes the following contributions.

- A privacy-budget allocation that makes conditional structure cheap. Public stratification costs nothing; histograms replace moment queries; one histogram block per outcome class costs what one pooled block does;

and parallel composition, under which statistics on non-overlapping groups each spend the full budget rather than sharing it, applies across disjoint cohorts and cells. The result is 6.7× more budget per released statistic than the moment-based implementation it replaced, at unchanged ϵ ; Section 4.8 states the comparison, which is not against MST or AIM.

- A decoding stage that reaches the release’s own fidelity without spending budget: exact-count batches, selection from a threefold pool by raking and refinement over every released cell, and a sub-bin rule that makes values inside released bins the release’s own (Sections 4.4 and 4.5).
- A head-to-head against the deployed mechanisms that reports fidelity and utility in the same table, against a real-sample floor and a no-information floor (a real sample of the same size, and the same data with its target permuted), with Holm-corrected families of tests (Section 6.1).
- Evidence that the two standard acceptance criteria are saturated, a concrete replacement criterion, and a matched control that separates a mechanism reading a release from one reciting its prior (Section 6.3); the controls that answer the reproducibility and contamination objections to a closed-weight generator are stated before the results (Section 5.6).
- A transmission test, which asks whether a relationship planted in the private data reappears in the synthetic output, showing that whether a private conditional relationship survives synthesis differs between the two mechanism families we tested, MST and PATE-CTGAN, at the same guarantee (Section 6.4).
- A utility transmission bound (Stage C): a budgeted, auditable bound on the gap between private and synthetic conditional rates, with floors and a ceiling built in and a refusal to report when it cannot discriminate (Sections 4.6 and 6.9).
- Auto-configuration; a membership-inference evaluation, in which attacks that try to tell whether a record was in the private data are validated on a positive control of real records passed off as synthetic; a reference deployment architecture with the trust boundary located precisely; a catalogue of the measurement artefacts that produced wrong conclusions along the way; and two Apache-2.0 implementations that enforce the guarantees stated here in code (Sections 6.7, 6.10, 7 and 9, and Appendix C).

A companion [technical report](#) contains every intermediate experiment, the per-dataset walkthroughs and the full defect catalogue. This paper reports the final mechanism and the evidence for it.

2. Background

2.1 Data and histograms

Definition 1 (Dataset). A dataset D is a multiset of n records over a schema with attributes $A = A_{num} \cup A_{cat}$ and a binary target y . Each attribute a has a public domain, an interval $[lo_a, hi_a]$ if numerical and a finite value set if categorical, and public bin edges E_a partition each numerical domain into intervals.

Definition 2 (Histogram and rate). $M_a(D)$ is the histogram of attribute a over E_a , or over its value set if a is categorical: a vector of counts, one per bin. For a cell c of the record space, $k_c(D)$ is the number of records in c with $y = 1$, and $p_c(D) = k_c(D) / |c|$ is the target rate in c .

A partition Π of the record space induced by a rule over public domains assigns every record to one part, $\Pi(x)$, as a function of x alone. Two properties of the schema are assumed public throughout, as in every marginal-based synthesiser: the attribute list and each attribute’s domain bounds. No quantity derived from private values is used to choose bins, bands or cells. The one exception is the auto-configurator’s column ranking, which is charged to the budget (Section 4.3).

2.2 Differential privacy

Two datasets D, D' are neighbours if one is obtained from the other by adding or removing one record.

Definition 3 (Differential privacy [13]). A randomised mechanism M satisfies ϵ -differential privacy if for all neighbouring D, D' and all sets S of outputs,

$$\Pr[M(D) \in S] \leq e^\epsilon \cdot \Pr[M(D') \in S]. \quad (1)$$

Proposition 1 (Laplace mechanism [13]). Let f be a function of D with L1 sensitivity $\Delta = \max_{D, D'} \|f(D) - f(D')\|_1$. Then $f(D) + \text{Lap}(\Delta/\epsilon)$, with the noise drawn independently per coordinate, satisfies ϵ -differential privacy.

A histogram over any number of bins has $\Delta = 1$, because one record moves exactly one count by one. A counting query has $\Delta = 1$ for the same reason. The mechanism is built on this fact: an entire distributional shape costs the same budget as a single count. The total error of a histogram still grows with its bin count, because every bin carries its own noise; what the sensitivity bound fixes is the budget, not the error.

Proposition 2 (Sequential composition [14]). *If $M_1, \dots, M_k$ satisfy $\epsilon_1, \dots, \epsilon_k$ -differential privacy and are run on the same data, their joint output satisfies $(\sum_i \epsilon_i)$ -differential privacy.*

Proposition 3 (Parallel composition [30]). *If $D_1, \dots, D_k$ are disjoint subsets of D defined by a data-independent rule and each M_i satisfies ϵ -differential privacy on D_i , the joint output satisfies ϵ -differential privacy.*

Proposition 4 (Post-processing [14]). *If M satisfies ϵ -differential privacy and g is any function, possibly randomised, that does not read D , then $g \circ M$ satisfies ϵ -differential privacy.*

Definition 3 also bounds any membership adversary. No test that decides whether a record is in D can have a true-positive rate exceeding its false-positive rate, which is its advantage, by more than

$$\frac{e^\epsilon - 1}{e^\epsilon + 1}, \quad (2)$$

which is 0.762 at $\epsilon = 2$. We use this bound as the reference for the measured advantages of Section 6.10.

2.3 Related work

Marginal and graphical-model methods. PrivBayes [52], MST [28], PrivMRF [7] and AIM [29] select low-order marginals under differential privacy and fit a graphical model with Private-PGM [27]. MST won the 2018 NIST differential privacy synthetic data challenge [37]. AIM is workload-adaptive and is the strongest of these.

Both MST and AIM are evaluated on marginal workload error. MST uses the NIST score at $\epsilon \in \{0.3, 1, 8\}$; AIM uses normalised L1 workload error over all-3-way, target and skewed workloads. Neither paper reports a downstream predictive-utility experiment. We state this as a scope observation rather than a criticism: these mechanisms target a different objective and attain it, and Section 6.1 shows them doing so.

The benchmark of Tao et al. [44], which does include a classification task, found the marginal methods ahead of the generative ones, and our Tables 3 to 5 reproduce that result for the baselines they share. A later benchmark by Chen et al. [10] reaches the same conclusion with a machine-learning utility score. It excludes language-model-based methods on the ground that their pretraining corpora would bias the evaluation, an objection Section 6.3 is designed to answer.

Generative models trained under differential privacy. DP-GAN [49], PATE-GAN [24], and DP-CTGAN and PATE-CTGAN [38] apply DP-SGD or PATE [35, 36] to a generative model, the last two over the CTGAN architecture [50]. Rosenblatt et al. [38] evaluate downstream utility with train-on-synthetic, test-on-real (TSTR) against train-on-real. We adopt their protocol.

Language models for tabular data. GReaT [5] fine-tunes a language model to emit rows and achieves high fidelity with no privacy guarantee, since the model memorises records. DP-LLMTGen [45] adds DP-SGD fine-tuning, which is private but expensive and still trains on the private data. DP-2Stage [3] reduces the cost of that fine-tuning by first training on public pseudo-data, but still trains on the private records. Curated LLM [39] uses a language model to augment small tabular datasets without a privacy guarantee, and conditions on the private data directly rather than on a release.

Private synthesis through model APIs. The closest line of work to ours also keeps the foundation model frozen and reaches it only through an inference API. Private Evolution [26, 48] generates candidate records from the model, privately votes on which candidates lie nearest to the private records, and iterates; it spends privacy budget on every round of votes. Swanberg et al. [43] adapt it to tabular data with a workload-based distance and find that API access to a strong model does not by itself improve on the marginal baselines. Tran et al. [46] extend it with evolutionary operators and private scoring. Their one-shot variants treat the model’s schema-only output as public data and spend the budget reweighting it to privately measured marginals, which is the nearest analogue to our selection step. The difference is that our release, not a later measurement, is what the model decodes, and the selection reads only that release.

CoRTeC differs in where the budget goes and how often it is spent. It spends the budget once, on a statistics release that names the conditional structure a downstream model needs, and then treats the model as a decoder of that release under exact counts and selection. The model is therefore never in the privacy loop; any number of datasets can be drawn from one release; and the privacy analysis is a composition argument over counting queries rather than over rounds of private selection. Table 1 summarises the positioning.

Table 1: Positioning. Every prior method except Private Evolution lets the generator see private data, and privacy depends on the mechanism that touches it: the training, or Private Evolution’s votes. CoRTeC trains nothing: it releases private statistics once and lets a frozen model decode them, so the privacy argument is a post-processing argument over the release. The trade-off is explicit. Any structure the released statistics do not imply comes from the model’s prior, which is the failure mode Section 6.4 is designed to detect.

method family	generator sees raw data?	where noise enters	utility in its own paper?	conditional structure
PrivBayes, MST, AIM, PrivMRF	yes (to fit)	selected marginals	no	only what the chosen marginals imply
DP-GAN, DP-CTGAN	yes (DP-SGD)	gradients	partially	learned, degraded by clipping and noise
PATE-GAN, PATE-CTGAN	yes (PATE on the discriminator)	teacher votes	yes	learned
GReaT	yes (fine-tuning)	none; not private	yes	learned, memorised
DP-LLMTGen, DP-2Stage	yes (DP-SGD fine-tuning)	gradients	yes	learned
Private Evolution (API-only)	no (private votes over candidates)	each round’s nearest-neighbour votes	yes	whatever the votes select; budget spent per round
CoRTeC (this work)	no	released statistics only	yes	released explicitly: a private conditional table and one histogram block per outcome class

3. Problem Setting and Threat Model

The task. Given a private dataset D with a binary target, a public schema and a budget ϵ_{total} , produce a synthetic dataset $\hat{D}$ of any requested size such that:

- (i) the whole procedure is ϵ_{total} -differentially private with respect to D ; and
- (ii) a model trained on $\hat{D}$ performs, on real held-out data (records no mechanism saw), as a model trained on a real sample of the same size would.

We measure (ii) directly, as TSTR under three student models, the classifiers trained on the synthetic data, against a matched real sample. We always measure fidelity beside it, because a method can score well on one and poorly on the other.

The trust boundary. Figure 1 shows where it lies. Everything to the left of the boundary runs inside the institution’s regulated zone and touches private records: the extract, the schema declaration and the release engine. The only object that crosses the boundary is the release R , a set of noisy counts. The generator, the selection step, the evaluation and every downstream use run to the right of the boundary, and read R and their own output only.

Whoever operates the generator, including a hostile endpoint, learns nothing that R does not already reveal, and R is ϵ_{total} -differentially private. This is what lets the model be a vendor-hosted endpoint: the privacy argument holds against a hostile endpoint by construction, because the request carries only R . What does not hold against a hostile endpoint is the compliance argument, which rests on tenant isolation, private networking, data residency and a business associate agreement. Section 7 states those requirements.

The adversary. For the guarantee, the adversary is unrestricted: Definition 3 bounds any function of the release and of everything derived from it. For the empirical evaluation of Section 6.10, the adversary sees $\hat{D}$ and a candidate record and must decide whether the record was in D . That measurement tests the implementation, not the mechanism, and cannot improve on the bound (2).

The privacy unit. ϵ protects a row. On data with one row per person, $\epsilon_{\text{person}} = \epsilon_{\text{row}}$, which is the case for Adult, the credit dataset, NHANES and every other dataset we use except one. On encounter-level data with repeated individuals, group privacy weakens the per-person guarantee by the maximum number of rows one person

contributes. Diabetes 130 has a mean of 1.42 rows per patient and a maximum of 40, so at $\epsilon_{\text{row}} = 2$ its worst-case per-person guarantee is 80, outside any range normally considered meaningful. This is equally true of MST or AIM run on the same data at the same row-level ϵ . Every figure we report from that dataset is a row-level figure.

The mitigation is a pre-processing step taken before the release, and its accounting is exact. Capping each person's contribution to their first C rows discards data, and the estimand becomes the retained rows rather than every encounter. On Diabetes 130 at a matched $\epsilon_{\text{person}} = 2$ it is 6.3 $\times$ more accurate than aggregating to one row per person (conditional error 0.0123 against 0.0780). The reference implementations require the schema to declare the maximum rows per person, and refuse a declared unit whose ϵ_{person} is vacuous unless the caller acknowledges it in the audit trail.

What the guarantee does not cover. The frozen model's pretraining corpus is not part of it. If a private record was in that corpus, it was compromised before CoRTeC ran. Language models are known to reproduce training data even under benign prompting [2]. What CoRTeC guarantees is that the generator learns nothing about D from CoRTeC; it cannot guarantee what the generator already knew. Section 6.3 measures the one consequence that would inflate our results, a prior that happens to be right about a public benchmark. Section 6.10 attacks the artefact the method publishes, which is where a memorised record would have to surface to cause harm.

4. The CoRTeC Mechanism

4.1 Overview




Figure 1: CoRTeC. The privacy budget is spent once, in Stage A. Everything to the right of the dashed line, the generator and every post-processing step, sees only released statistics, so it contributes nothing to the privacy cost and may be repeated without limit.

The mechanism has three stages.

Stage A (Algorithm 1) is the only code that reads D . It partitions the record space into cohorts by a public rule. Inside each cohort of at least $n_{\min}$ records it releases a noisy cohort size, a noisy class balance, and one noisy histogram per attribute and per outcome class. It then releases, for each level of a nested conditional hierarchy, a noisy positive count and a noisy size for every cell of at least $n_{\min}$ records. The output is the release R .

Stage B reads R and nothing else. It:

- allocates rows to cohorts by released size;
- apportions exact per-bin counts from the released histograms;
- asks a frozen language model for batches of rows that carry exactly the counts still owed (Algorithm 3);
- generates a pool k times larger than the requested size and keeps the m rows whose cell counts best match R (Algorithm 4); and
- redraws each kept value uniformly inside its released bin wherever the release describes the class shape at that resolution.

Stage C (Algorithm 5) is optional and spends a separately declared budget. It releases a Laplace estimate of each cell's private target rate and turns it into a simultaneous bound on how far the synthetic data's rates lie from the private ones. A deployment can then attach a quantified utility claim to a release package without exposing the private data.

An auto-configurator (Algorithm 2) derives the cohort rule and the conditional hierarchy from the schema, the budget and the requested size, and charges the one step that reads private data.

4.2 Stage A: the release

Algorithm 1: CoRTeC-Release

Input: private D ; public schema (domains, bin edges E , stratification rule Π , conditional levels $L_0 \subset L_1 \subset \dots \subset L_k$); budget ϵ_{total} ; conditional share α ; count share γ ; suppression floor $n_{\min}$

Output: release R

- (1) $\epsilon_{\text{count}} \leftarrow \gamma \cdot \epsilon_{\text{total}}$; $\epsilon_{\text{rest}} \leftarrow \epsilon_{\text{total}} - \epsilon_{\text{count}}$; $\epsilon_{\text{marg}} \leftarrow (1 - \alpha) \cdot \epsilon_{\text{rest}}$; $\epsilon_{\text{cond}} \leftarrow \alpha \cdot \epsilon_{\text{rest}}$
 - (2) $q \leftarrow |A_{\text{num}}| + |A_{\text{cat}}| + 1$ (queries per cohort; sequential within a cohort)
 - (3) $\epsilon_q \leftarrow \epsilon_{\text{marg}} / q$ (cohorts are disjoint: parallel across Π)
 - (4) $\epsilon_L \leftarrow \epsilon_{\text{cond}} / |L|$ (levels overlap: sequential across levels)
 - (5) For each cohort P the public rule Π can form, holding records or not:
 - (6) $n_p \leftarrow |P| + \text{Lap}(1/\epsilon_{\text{count}})$; if $n_p < n_{\min}$, continue (the cohort is not released); release n_p
 - (7) Release the two-bin count histogram of y on P , each count $+ \text{Lap}(1/\epsilon_q)$
 - (8) If both noised class counts of line 7 are at least $n_{\min}$: (class-conditional blocks; a noisy threshold)
 - (9) For $c \in \{0, 1\}$ and $a \in A$: release $M_a^{\sim}(P, c) \leftarrow M_a(P \cap \{y = c\}) + \text{Lap}(1/\epsilon_q)$
 - (10) $M_a^{\sim}(P) \leftarrow$ mixture of $M_a^{\sim}(P, c)$ under the released class balance
 - (11) Else: for $a \in A$, release $M_a^{\sim}(P) \leftarrow M_a(P) + \text{Lap}(1/\epsilon_q)$ (pooled block)
 - (12) For each level $\ell \in L$ and each cell c of ℓ 's public domain, holding records or not:
 - (13) $k_c^{\sim} \leftarrow k_c(D) + \text{Lap}(2/\epsilon_L)$ and $n_c^{\sim} \leftarrow |c| + \text{Lap}(2/\epsilon_L)$; if $n_c^{\sim} < n_{\min}$, continue (the cell is not released)
 - (14) $\rho_c^{\sim} \leftarrow \text{clip}(k_c^{\sim} / \max(n_c^{\sim}, n_{\min}), 0, 1)$ (post-processing of two counts)
 - (15) Return R : every released quantity, with its ϵ , sensitivity and composition rule
-

Five decisions in Algorithm 1 make the method work, and each rests on a sensitivity argument.

Public stratification (line 5). Cohorts come from a rule fixed over public domains, so $\Pi(x)$ is a deterministic function of x 's own record, and forming cohorts consumes no budget. This replaces private clustering, which spends budget and, in our measurements, produced degenerate cohorts of 3 and 8 records.

Histograms, not moments (lines 9 and 11). A histogram has L1 sensitivity 1 regardless of its bin count, since one individual moves exactly one bin. An entire distributional shape therefore costs the same budget as a single count, and moments are recovered from the released histogram for free. Under the moment formulation, by contrast, the standard-deviation query has sensitivity $(hi - lo)/(2\sqrt{n})$, and at realistic budgets that produced released values larger than the attribute's entire range: at a cohort size of 20, a released standard deviation of 693.80 against a true value near 13.

Class-conditional histograms (lines 8 to 10). A pooled cohort histogram says what the cohort looks like, and nothing about how any feature relates to the target outside the conditional hierarchy. The generator fills that in from its prior, and on the finance dataset the filled-in columns measurably degraded the downstream model (Section 6.2). Partitioning each cohort by the target, and releasing one histogram block per (cohort, class), gives the generator the class-conditional marginals a classifier needs, for every column. The two class blocks are disjoint, so they compose in parallel, and each spends the same ϵ_q per column that the pooled block did. The pooled histogram is their mixture under the released class balance, which is post-processing. Where a class falls below $n_{\min}$, the cohort keeps the pooled block.

A conditional table over a disjoint partition (lines 12 to 14). Because the cells of one level partition D , they satisfy parallel composition: each receives the full ϵ_L , however many cells the level contains. A cell's rate is the ratio of two counts, each carrying $\text{Lap}(2/\epsilon_L)$. Its noise is therefore of order $2/(|c| \cdot \epsilon_L)$, and its accuracy is governed by cell support, not by the number of cells. Conditional structure is therefore cheap to release, and that observation is the basis of the method.

We do not noise the rate directly as a bounded mean. That mechanism's scale, $1/(|c| \cdot \epsilon_L)$, depends on $|c|$, which is itself private under add/remove adjacency. Two Laplace densities with different scales have an unbounded likelihood ratio in one tail, so the mechanism is not pure ϵ -differentially private. Two counts of sensitivity 1 at a public scale are.

The published cohort size (line 6). The generator allocates rows to cohorts in proportion to size, so the size must be released. It is a private count, noised at $\text{Lap}(1/\epsilon_{\text{count}})$, taken off the top of ϵ_{total} before the split (Algorithm 1, line 1) and clamped at n_{min} . A cohort is released only when it holds at least n_{min} records, so any lower published value is impossible under the release’s own rule. Without the clamp, at $\epsilon = 0.3$ on NHANES the youngest age band’s noised size clipped to zero, and the band vanished from the output while every per-row check passed.

The conditional share. With one histogram block per outcome class, the release already carries most of what a classifier needs. The conditional table’s share α can then fall from a half to a fifth without measurable loss. The histograms receive that budget, and the release’s own 1-way error against the training data falls from 0.029 to 0.020 on Adult and from 0.017 to 0.013 on finance. $\alpha = 0.2$ is the shipped default; γ is 0.02 in the research pipeline and 0.05 in the reference implementation (Table 29).

4.3 Auto-configuration

Every early result in this project depended on a hand-chosen configuration: which columns the conditional table conditions on, how many levels it carries, and how cohorts are formed. Choosing those columns after inspecting the private data is an uncharged, data-dependent decision, and it means the method cannot be deployed without a statistician. Algorithm 2 derives the whole configuration from the declared schema, the target, the budget and the number of records requested.

Algorithm 2: CoRTeC-Autoconfigure

Input: private D of size n ; public schema; target y ; ϵ_{total} ; requested size m ; noise-floor multiple M

Output: stratification rule Π , conditional levels L , budgets ϵ_{sel} and $\epsilon_{\text{release}}$

(1) $m_{\text{cand}} \leftarrow$ number of candidate columns; $L \leftarrow$ median level count of the candidates; $|Y| \leftarrow$ number of target classes

(2) $f \leftarrow \text{clip}(M \cdot m_{\text{cand}} \cdot L \cdot |Y| / n, 0.05, 0.30)$; $\epsilon_{\text{sel}} \leftarrow f \cdot \epsilon_{\text{total}}$; $\epsilon_{\text{release}} \leftarrow \epsilon_{\text{total}} - \epsilon_{\text{sel}}$

(3) For each candidate column a : (the only step that reads D)

(4) $T_a^* \leftarrow$ contingency table of bands(a) $\times y$ on D , each cell $+ \text{Lap}(m_{\text{cand}}/\epsilon_{\text{sel}})$

(5) $\text{score}_a \leftarrow$ mutual information of T_a^* (post-processing)

(6) Coarsen a into at most four bands by its noisy positive rate, read from T_a^*

(7) Rank the candidates by score; choose the stratification column and the conditioning columns

(8) Add conditioning columns while every cell still expects at least 8 records under m , preferring the depth closest to 20 records per cell, divided by the cohort count

(9) Return $\Pi, L, \epsilon_{\text{sel}}, \epsilon_{\text{release}}$

Column ranking is the only private step, and it is charged. Each candidate is scored from one noised contingency table of its bands against the target. A record occupies exactly one cell, so the table’s L1 sensitivity is 1 however many cells it has. The tables are not disjoint across candidates, since every record appears in all of them, so they compose sequentially at $\epsilon_{\text{sel}}/m_{\text{cand}}$ each. Everything after the noised counts, namely the mutual-information computation, the coarsening and the ranking, is post-processing. A greedy conditional-MI selector was tried and reverted for a cardinality bias (technical report, H.10).

Richness needs no private input at all. A conditional table’s usable resolution is set by how many records land in each cell; cell counts are a function of public cardinalities, and the number of records requested is a public choice.

The selection budget is adaptive because selection is meaningful only while a column’s expected cell count exceeds the Laplace noise on it. Writing f for the share of ϵ_{total} spent on selection, and requiring the expected count per cell to exceed the noise scale by a factor M ,

$$\frac{n}{L \cdot |Y|} \geq M \cdot \frac{m_{\text{cand}}}{f} \Leftrightarrow f \geq \frac{M \cdot m_{\text{cand}} \cdot L \cdot |Y|}{n}, \quad (3)$$

which is line 2 after clipping the share to $[0.05, 0.30]$. $M = 1$ is the shipped value, and every quantity in (3) except n comes from the declared schema. Small datasets therefore spend more on selection, which is correct: a smaller release needs less budget to describe. Under a fixed 5% share, three of six datasets it had never seen declined to configure at all (Section 6.7).

4.4 Stage B: generation with exact counts

Algorithm 3: CoRTeC-Generate

Input: release R ; requested size m ; pool factor k ; batch size B ; frozen model G

Output: pool $\hat{D}$ of about $k \cdot m$ rows

- (1) For each cohort P in R : $m_p \leftarrow k \cdot m \cdot n_p / \sum_p n_p$ (rows by released size)
 - (2) $T_p \leftarrow \text{Apportion}(m_p; \text{released class balance}, M_a(P, c) \text{ for all } a, c)$ (exact per-bin, per-category and per-class counts)
 - (3) While rows are still owed to P :
 - (4) $b \leftarrow \min(B, \text{rows owed})$
 - (5) $\text{owed} \leftarrow \text{Apportion}(b; T_p - \text{counts of the rows already accepted for } P)$
 - (6) $\text{rows} \leftarrow G(\text{prompt}(R, P, b, \text{owed}))$ (the prompt carries R and the counts, never D)
 - (7) Accept the rows that parse, lie inside their domains and carry declared categories; append them to $\hat{D}$
 - (8) Return $\hat{D}$
-

Asked to reproduce a histogram stated as shares, a frozen model reproduces it approximately, and the rows it emits carry that approximation plus the sampling noise of any batch. Asked instead for exact counts, it can satisfy them. A 25-row batch told the number of rows it must produce per bin and per category reproduces every count line exactly on the frontier models we measured; the same batch given shares matches about two thirds of them.

The counts are apportioned from the released histograms for the cohort as a whole (line 2), so they carry no more information than the release does. Each batch asks for the counts the cohort still owes after the rows already accepted (line 5), so a batch that returns more or fewer valid rows than asked cannot leave the cohort's totals short. The batch size is 25 and the pool factor is 3 by default.

In a cohort that carries class blocks the apportionment in line 2 is per class, and the prompt states the counts per class: among the batch's positives, the rows per bin and per category from the positive block; among its negatives, the same from the negative block. The prompts behind the tables of Section 6.1 stated those counts as totals over the two classes, with only the number of positives stated separately, which left each class's marginals to the generator's reading of the class blocks; the open-weight comparison (Table 34) found that one generator followed them and another did not. From this release the per-class statement is the default, and `--no-quota-by-class` restores the earlier one.

The prompt (Appendix A) is versioned and hash-locked in the reference implementation, because two of its elements are essential and their removal is not visible in the output. The first is the conditional target table, which is the only channel through which the conditional structure reaches the generator. The second is the instruction to follow the released statistics even where they contradict the model's expectations; without it, a model reconciles the release against its prior and emits the prior. Section 6.3 measures the first.

4.5 Selection, and values below bin resolution

Algorithm 4: CoRTeC-Select

Input: release R ; pool $\hat{D}$; requested size m

Output: synthetic dataset D^* of exactly m rows

- (1) Require that every cohort P holds at least $1.1 \cdot m \cdot n_p / \sum n$ rows of $\hat{D}$ (coverage guard)
 - (2) $w \leftarrow$ inclusion weights from iterative proportional fitting of $\hat{D}$ to every released cell: cohort sizes, class balances, one histogram per cohort, class and attribute; a category the release suppressed receives weight 0
 - (3) $D^* \leftarrow$ a systematic sample of m rows of $\hat{D}$ under w (rake)
 - (4) Repeat: swap a row of D^* for a row of $\hat{D} \setminus D^*$ whenever the swap lowers the weighted L1 distance between the cell counts of D^* and those of R , until no swap improves it (refine)
 - (5) For each cohort P with class-conditional blocks, each $a \in A_{\text{num}}$ and each row of D^* in P : redraw the value uniformly inside its released bin intersected with its stratification band; integer attributes draw integers (sub-bin rule)
 - (6) Return D^*
-

Selection from a pool (lines 2 to 4). The inclusion weights come from iterative proportional fitting, the raking procedure of Deming and Stephan [11], applied to the generated pool against every released cell. Exact-count batches match the release closely but not exactly, and any m rows drawn at random from a faithful pool carry the sampling error every m -record sample carries. Generation is free in ϵ , so the pipeline asks for k times the rows it needs and keeps the m whose cell counts match the release.

The pooled marginals are weighted above the per-cell counts. A cohort whose release carries only a pooled block is constrained at cohort level, not per class, because imposing a pooled histogram on each class would erase the feature-to-target structure the release spent budget on. The cost of selection is k times the generation spend.

The coverage guard (line 1). Selection can only choose among rows that exist. A pool that reached its spend cap before every cohort was complete produced a draw whose two lowest-education cohorts held 63% of the rows against a released share of 40%. Every per-row check passed; the draw simply carried the pool's imbalance. Both implementations now require every cohort to be covered by at least $1.1\times$ the rows it owes before selecting, and the tool refuses a pool that is not.

Values below bin resolution (line 5). A released histogram fixes how many rows fall in each public bin and nothing finer, so where a value lies inside its bin is never released information. In a cohort that carries class-conditional blocks, the class shape is the release's at bin resolution, and whatever the generator does below it comes from its prior. On NHANES that prior separated the outcome classes about twice as far as the data does inside each bin: a BMI gap of 6.2 between diabetic and non-diabetic rows against 3.1 in the training data, and a positive diastolic effect the data does not have. A bin-level selection cannot see this. A tree student that splits on thresholds is indifferent to it; a linear student that fits a slope is not.

In those cohorts every numeric value is therefore redrawn uniformly inside its released bin, intersected with the row's stratification band so that no row changes cohort. Every bin count under the release's bins is unchanged by construction. In a cohort with only a pooled block, the generator's placement is the only carrier of the class signal, and it is kept; on the two pooled arms we measured, replacing it cost the tree students up to 0.03 AUC. The rule reads the release and the rows, has no parameter, and is post-processing.

4.6 Stage C: the utility transmission bound

Sections 6.3 and 6.4 measure, with access to the private data, whether the released conditional structure reaches the output. A deployment needs that measurement as a budgeted artefact a third party can inspect without that access. For each released cell c , the private data has a true positive rate p_c and the synthetic data a rate q_c . q_c is a function of the synthetic output alone, so it is public and free; p_c is private. Stage C releases a Laplace estimate $\hat{p}_c$ at a declared budget ϵ_{cert} and turns its noise into a one-sided confidence bound.

Algorithm 5: CoRTeC-Bound

Input: private D ; synthetic $D^{\wedge*}$; the released cells $c_1, \dots, c_k$ of the finest level with their released rates $\tilde{\rho}_c$ and base rate $\tilde{\rho}$; suppression floor $n_{\min}$; budget ϵ_{cert} ; confidence $(1 - \alpha)$; minimum synthetic rows per cell $m_{\min}$; optionally a tolerance τ

Output: a simultaneous bound B_c per cell, a verdict, or a refusal

- (1) For each cell c : $q_c \leftarrow$ positive rate of $D^{\wedge*}$ in c (public)
 - (2) For each cell c : $\hat{p}_c \leftarrow k_c(D) / \max(|c|, n_{\min}) + \text{Lap}(1/(n_{\min} \cdot \epsilon_{\text{cert}}))$ (the rate over the public floor, as Algorithm 1 releases its rates; cells are disjoint: parallel across cells)
 - (3) For each cell c : $B_c \leftarrow \lfloor \hat{p}_c - q_c \rfloor + \ln(k/\alpha) / (n_{\min} \cdot \epsilon_{\text{cert}})$
 - (3') If no τ was given: $\tau \leftarrow \ln(k/\alpha) / (n_{\min} \cdot \epsilon_{\text{cert}}) + \frac{1}{2} - \max_c |\tilde{\rho}_c - \tilde{\rho}|$ (released quantities only: post-processing)
 - (4) Repeat lines 1 and 3, against the same $\hat{p}_c$ released once at line 2, for a real hold-out sample in place of $D^{\wedge*}$ (the ceiling) and for the same sample with its target permuted (the floor)
 - (5) If the ceiling's largest B_c exceeds τ or the floor's does not: Return "this test did not discriminate", no verdict
 - (6) If any released cell holds fewer than $m_{\min}$ rows of $D^{\wedge*}$: Return "insufficient synthetic support", no verdict, and every B_c
 - (7) Return within bound if $\max_c B_c \leq \tau$, else outside tolerance; report every B_c
-

With probability at least $(1 - \alpha)$, simultaneously over all k released cells,

$$|p_c - q_c| \leq |\hat{p}_c - q_c| + b_c \cdot \ln(k/\alpha), b_c = \frac{1}{n_{\min} \cdot \epsilon_{\text{cell}}}, \quad (4)$$

where $\epsilon_{\text{cell}} = \epsilon_{\text{cert}}$ because the cells partition the data. The rate is taken over $\max(|c|, n_{\min})$ (line 2), as Algorithm 1 takes its released rates, so its sensitivity is at most $1/n_{\min}$ for every cell whatever its true size, including a cell that the noisy gate of Algorithm 1 released below the floor, and the scale depends on nothing private. Such a cell reads at $|c|/n_{\min}$ of its true rate, a downward bias that is rare and bounded; none of the cells behind Table 23 is below the floor. The bound is conservative by a factor $n_c / n_{\min}$ on each cell, which is the cost of using the public floor. The union bound over cells makes the guarantee simultaneous rather than per cell. The k rate queries compose in parallel, so a deployment that bounds at ϵ_{cert} has spent $\epsilon_{\text{release}} + \epsilon_{\text{cert}}$ in total.

The reference implementation reports both (`cortec.bound` in the framework, and `certify.py` in the research repository, which produced the results below). Lines 4 and 5 are the floor-and-ceiling discipline of Section 5.3 applied to the bound itself: a real sample must clear the tolerance and a permuted one must not, or the procedure issues no verdict. The tolerance is derived from the release unless one is given. The permuted floor's bound in a cell converges, as the synthetic sample grows, to the gap between that cell's rate and the base rate plus the noise term, so any tolerance at or above the largest such gap plus the noise term lets the floor through at a large enough n ; line 3' places it halfway between the noise term and that limit, from released quantities only. A fixed tolerance chosen by repetition on the private data, which an earlier version of this procedure used, is a calibration the procedure cannot ship. Line 6 withholds the verdict while any released cell holds fewer than $m_{\min} = 20$ synthetic rows: such a rate moves by a third on three rows, and (4) carries no sampling term for it.

The bound speaks to utility only. It says how much conditional structure survived generation, and nothing about re-identification risk. Section 7 keeps it out of the compliance mapping for that reason.

4.7 Privacy analysis

Theorem 1 (Privacy of CoRTeC). *Algorithms 1, 3 and 4 together satisfy ϵ_{total} -differential privacy. Algorithm 2 followed by them satisfies $(\epsilon_{\text{sel}} + \epsilon_{\text{release}})$ -differential privacy, which equals ϵ_{total} .*

Proof. Consider neighbouring D, D' differing in one record x .

(i) *Stratification is free.* Π is a function of public attribute domains only, so $\Pi(x)$ is computed from x 's own attributes without reference to any other record. The partition structure is data-independent, and releasing it costs nothing.

(ii) *Within a cohort, sequential composition.* Fix a cohort P . Each released histogram is a counting query of L1 sensitivity 1. x contributes to exactly one bin of one attribute, so removing it changes that histogram's L1 norm by 1 and every other histogram not at all. By Proposition 1 the Laplace mechanism at scale $1/\epsilon_q$ gives ϵ_q -differential privacy per query. Under the pooled block (line 11) the q queries on P compose sequentially (Proposition 2) to $q \cdot \epsilon_q = \epsilon_{\text{marg}}$. Under the class-conditional blocks (line 9), P is partitioned by y , so x lies in exactly one of $P \cap \{y=0\}$ and $P \cap \{y=1\}$. It is touched by the class-balance query of line 7 and by the $q - 1$ histograms of its own block, and by nothing in the other block. That is a chain of q queries and the same $q \cdot \epsilon_q$. The two blocks are disjoint and compose in parallel (Proposition 3). The pooled histogram of line 10 is a function of released quantities only.

(iii) *Across cohorts, parallel composition.* The cohorts are disjoint and defined by a public rule. Record x lies in exactly one, so it can influence only that cohort's queries; the others are identical on D and D' . By Proposition 3 the cost across cohorts is ϵ_{marg} , independent of $|\Pi|$.

(iv) *Within a conditional level, parallel composition.* The cells of level ℓ partition D , so the same argument applies, and level ℓ costs ϵ_L however many cells it contains. Within a cell c we release two counting queries, the positive count k_c and the cell size $|c|$. Each has L1 sensitivity exactly 1 under add/remove adjacency, and each is noised at $\text{Lap}(2/\epsilon_L)$, a scale that depends on nothing private. They touch the same records, so they compose sequentially to ϵ_L per cell. The published rate $\tilde{\rho}_c = k_c / \max(\tilde{n}_c, n_{\min})$ is a function of two released quantities and the public floor, so it is post-processing (Proposition 4), as is clipping to $[0, 1]$.

(v) *Across levels, sequential composition.* Levels of differing granularity describe the same individuals, so they are not disjoint and compose sequentially: $|L| \cdot \epsilon_L = \epsilon_{\text{cond}}$. The reference implementation additionally spends a count family on every cell's support, inside ϵ_{total} : the count share of Table 29, half to cohort sizes and half to cell supports, the cell half divided across the declared levels. It then splits ϵ_{cond} across the levels in which at least one noised support

reaches $n_{\min}$; that set is a function of released counts, so the split is post-processing. No reported release uses it: every table in this paper was produced by the research path, which splits ϵ_{cond} across the $|L|$ declared levels as line 4 states. A split across levels found viable from exact counts would not be sound.

(vi) *The published cohort size.* $|P|$ is a counting query of sensitivity 1, noised at $\text{Lap}(1/\epsilon_{\text{count}})$. Cohorts are disjoint, so the cost across Π is ϵ_{count} by parallel composition. It composes sequentially with the q queries on the same cohort. Every $n_{\min}$ decision in Algorithm 1 compares a noised count with the public floor (lines 6, 8 and 13), and every cohort and cell of the public domains is queried whether or not it holds a record, so which groups appear in R is a function of released quantities and public constants alone, and is post-processing by Proposition 4.

(vii) *Stage B is post-processing.* The row allocation (Algorithm 3, line 1) reads released sizes. The per-bin counts a batch is asked for (line 2) are apportioned from released histograms. The counts still owed (line 5) are a difference of released targets and generated rows. The prompt carries R and those counts. The model G is frozen and reads only the prompt. The acceptance rule of line 7 reads public domains. The inclusion weights, the rake, the refinement and the sub-bin redraw of Algorithm 4 read R , the generated rows and independent randomness. By Proposition 4 none of these increases the privacy loss, at any pool factor k and for arbitrarily many draws.

Summing the dependent components, $\epsilon_{\text{count}} + \epsilon_{\text{marg}} + \epsilon_{\text{cond}} = \epsilon_{\text{total}}$. Stage C, when run, adds ϵ_{cert} : its k Laplace queries are counting-rate queries over $\max(|c|, n_{\min})$, of sensitivity at most $1/n_{\min}$ on disjoint cells whatever their true sizes, at a public scale, so by Proposition 3 they cost ϵ_{cert} together. The bound B_c and the verdict are functions of the released p_c^* , the synthetic output and public quantities. The discrimination check of line 4 reads a real hold-out sample that the release did not use; it is uncharged, and it decides whether a verdict is issued, not what the bound is. Under auto-configuration the m_{cand} contingency tables of Algorithm 2 are counting queries of L1 sensitivity 1 on the same records and compose sequentially to ϵ_{sel} ; everything downstream of their noised counts is post-processing. The release that follows spends $\epsilon_{\text{release}}$, so the total is $\epsilon_{\text{sel}} + \epsilon_{\text{release}} = \epsilon_{\text{total}}$. ■

What the theorem does not cover, and what the reported tables carry. The theorem covers the $n_{\min}$ decisions as Algorithm 1 makes them. The releases behind the CoRTeC rows of Tables 3 to 6 were produced under that rule: every cohort, class block and cell was released only when its charged, noised count reached $n_{\min}$, and each release file records the gate it was made under. The releases behind the earlier-configuration arms of Section 5.5, the second-vendor arms at minimal reasoning, the equivalence test and the ϵ sweep were produced before it, by comparing the exact count with $n_{\min}$: a data-dependent decision outside the accounted budget, which is the practice of the marginal-synthesis literature and of the MST and AIM reference implementations, whose rows therefore carry the gate outside their ϵ ; a recent audit of those implementations finds their empirical privacy close to the stated guarantee [18]. The current CoRTeC rows are the more conservative side of that comparison. We measured how far the two rules differ on the earlier releases, which spend the same budget and draw the same noise under either rule. The noisy threshold reproduces every gate decision of the earlier Adult release with probability 0.26, of the earlier finance release with probability 0.24, and of the earlier NHANES release with probability 0.70 (technical report, J.5). Where the rules differ, the difference is a cohort whose minority class holds 149 records against a floor of 150 and is released pooled rather than split, or a finance cell of 139 to 148 records that the exact rule withholds and the noisy one releases about one time in four. The regenerated Tables 3 to 6 therefore differ from the earlier build's by those decisions and by draw-to-draw variation; the arms still on earlier releases are on the replication list of Section 10. The hold-out sample behind the discrimination check of Algorithm 5 is read uncharged, and the record count n that Algorithm 2 reads to set the selection share is treated as public.

The earlier-configuration arms of Section 5.5 were released by an earlier rate mechanism that noised each conditional cell's rate at a scale set from the true cell size, which step (iv) above rejects. Per conditional level that mechanism is (ϵ_L, δ) -differentially private rather than pure ϵ_L , with δ computed exactly at 1.5×10^{-7} for the $n_{\min} = 150$ floor every reported release used. That pipeline also published per-cohort counts exact for most of the project; rebuilding every affected draw under noised counts moved no metric by more than 0.0005 (technical report, J.3). Every release path now implements that mechanism; the inversion test and the Adult sweep were re-run on GPT-5 under it (Sections 6.3 and 6.4), and the remaining earlier-configuration arms are on the replication list of Section 10.

The floating-point attack of Mironov [31] on the Laplace mechanism applies to every implementation in the comparison, including ours. It is declared as an open gap in the release's own audit block.

4.8 What the allocation achieves

The $6.7\times$ figure is measured against this project’s own first implementation, not against MST or AIM, which release different statistics: private clustering for cohorts, a mean and a standard-deviation query per attribute, and basic composition across cohorts. Against that baseline the same ϵ_{total} yields an ϵ per released statistic of 0.0667 against 0.0100, a $6.7\times$ improvement. In accounting terms it is the gain from parallel composition over disjoint cohorts and cells and from one histogram query in place of two moment queries. The realised per-query budget on the 15-column Adult schema at $\alpha = 0.5$ is 0.0653, because the cohort-size query of line 6 takes its 2% first; on the same footing the improvement is $6.5\times$.

The budget is verified by instrumentation rather than by re-deriving a model of it. A test patches the Laplace mechanism inside the release path and tallies what is actually spent, asserting exactly ϵ_{total} on three auto-configured schemas and at three budgets.

A tighter accountant would not help. Advanced composition [15] and concentrated differential privacy [6] loosen the bound by 16 to 31% at the chain lengths this method reaches, and only cross over past 27 queries. Those chain lengths are 15 marginal queries per cohort on the Adult schema, or 18 once its three conditional levels are counted. No Algorithm 1 release in this paper carries a conditional hierarchy deeper than 3 levels, or deeper than 2 at the shipped n_{min} ; the hybrid tables of Section 8.2 are budgeted separately and are named by the number of factors in their finest cell.

5. Experimental Setup

5.1 Datasets

Table 2: Datasets. The three in bold carry the head-to-head of Section 6.1.

dataset	domain	records	attributes	positive rate	rows per person	role
NHANES 2017–2018 [9]	healthcare (examination and laboratory)	3,749	10	14.2%	1	primary clinical dataset
UCI Adult [12, 25]	census	32,561	15	24.1%	1	comparability anchor; AIM’s own primary dataset
Default of credit card clients [51]	finance	30,000	15	22.1%	1	second regulated domain
Diabetes 130-US hospitals [42]	healthcare (administrative)	101,763	19	11.2%	mean 1.42, max 40	ϵ sweep at scale; transmission; membership inference
renal registry (constructed)	synthetic clinical	20,000	10	14.9%	1	contamination control (Section 6.3)
six untouched benchmarks	3 health, 3 finance	303–45,211	8–20	6.0–53.1%	1	auto-configuration generalisation (Section 6.7)

NHANES 2017–2018 is the primary clinical dataset: a national health examination survey of physical measurements and laboratory assays, obtainable with no application. We join the demographic, glycohaemoglobin, body-measures and blood-pressure files on the respondent identifier and restrict to adults aged 18 to 80. The target is $\text{HbA1c} \geq 6.5\%$, the American Diabetes Association’s diagnostic threshold [4], which makes this an undiagnosed-diabetes screening task on laboratory values rather than on billing codes. Bin edges are public clinical knowledge (WHO BMI categories, ACC/AHA blood-pressure stages), not quantiles of the file.

Adult is the head-to-head anchor, the only schema on which every mechanism we compare completes. The credit dataset is the second regulated domain. Diabetes 130 is hospital administrative data at scale, with 81,410 training records; it carries the ϵ sweep on a large dataset, the transmission sweep and part of the membership-inference evaluation. It is encounter-level, so every figure from it holds under a row-level guarantee (Section 3).

Each dataset is split once into a training set, which every mechanism sees, and a held-out test set, which only the evaluator sees. There are 26,048 training rows on Adult, 24,000 on finance and 2,999 on NHANES.

5.2 Baselines

We compare against the three families an institution would realistically choose between: the marginal methods MST and AIM; the DP-SGD generative model DP-CTGAN; and the PATE generative models PATE-CTGAN and PATE-GAN. All run through smartnoise-synth [34] at matched ϵ . Numerical columns are pre-binned using the same public bounds CoRTeC assumes, so no method gains an advantage from a different discretisation. All run at library defaults at $\epsilon = 2$ on the training split and are sampled at the same n as CoRTeC.

An unconditioned “header-only” prompt, the same frozen model given nothing but the column names, appears as a control and not as a competitor. It carries no privacy guarantee. Its role is to establish that CoRTeC’s output depends on the released statistics rather than on the model’s prior. Two forms appear. The header-only control gives the model only the column names; it is the control behind the aggregate-utility numbers of Section 6.3. The matched header-only control is CoRTeC’s own prompt with the released blocks removed and nothing else changed (Appendix A); it is the control behind the inversion test and the registry diagnostic of Section 6.3.

5.3 Metrics, and the floor-and-ceiling discipline

We report:

- marginal fidelity: 1-way and 2-way total variation, meaning half the summed absolute difference between two histograms, the latter over all column pairs;
- conditional fidelity: error in $P(\text{target} \mid \text{group})$ over the cohort bands of the stratification rule (“seen”: the groups every release describes, and not the conditional cells, which Stage C scores) and over strictly held-out group families sharing no column with the conditioning (“held-out”);
- AIM’s own 3-way workload error where stated; and
- utility: TSTR AUC under logistic regression, random forest and gradient boosting, each trained on the synthetic data and tested on the real held-out split.

Fidelity and utility appear in the same table for every condition, because a method can score well on one and poorly on the other, and both marginal baselines do.

Two references accompany every table. The *real-sample floor* is a genuine draw of n real training records. No synthetic method can be expected to exceed it at that n , and it is the only sensible target. The *permuted-target floor* is real data with the target column permuted. It has identical marginals and zero predictive content, and is therefore the score of data that carries no usable information. Any metric that fails to separate these two has no power, and we check that before drawing conclusions (Section 6.3). The *train-on-real ceiling* trains the students on the entire training set.

Evaluating against explicit reference points rather than a bare threshold is the discipline DPBench argues for [19], and it caught the founding defect of this project. Our original primary metric scored the real-data ceiling and the unconditioned baseline identically, so there was nothing for any method to improve, and a verdict had been drawn from it before the floors were checked (Section 9). The real-sample floor is drawn afresh for each table at that table’s n and draw count, so its value varies across tables by design. Comparisons are made at matched n .

Every metric is computed by one implementation that bins numerical columns with the public bin edges every method is fed. One convention is declared. The evaluator’s intervals are right-closed, while the release, the selection step and the baselines’ discretisation are left-closed, so an integer that lies exactly on an edge counts in different bins under the two. The effect is small and falls on every method. On the earlier Adult release, 1-way error under the release’s convention is 0.020 for CoRTeC, 0.015 for MST, 0.030 for AIM and 0.043 for a real sample, against 0.029, 0.024, 0.037 and 0.043 under the evaluator’s. Every synthetic-output number in this paper is the evaluator’s; a release’s own distance from the training data (Section 6.1, Table 9) is stated under the release’s convention. The ordering of methods is the same under either.

5.4 Statistics

Point estimates are means over draws. Differences between conditions are tested with Welch’s t-test on the per-draw values and corrected with Holm’s procedure [20] over each family of tests, a family being the seven metrics of one baseline on one dataset. Adjusted p-values are Holm’s step-down values. Where a rank test is reported, its smallest

attainable p-value at the draw counts in hand is reported beside it: at small group sizes it is the design, not the data, that limits the statistic. Confidence intervals on the headline equivalence test are bootstrap intervals over draws (10,000 resamples).

All CoRTeC draws within a condition come from one release and one generator, so they replicate the generation step. Releases are redrawn only for the transmission sweeps. Draws from different generators are never pooled, because the generator is itself a variable under study (Section 6.6).

5.5 The configuration reported

Unless a table says otherwise, every CoRTeC row is the shipped configuration:

- the class-conditional release of Algorithm 1 at $\epsilon = 2$ with $\alpha = 0.2$ and $n_{\min} = 150$;
- exact-count batches of 25 rows;
- a 3× pool (2× on NHANES) selected to the release with the sub-bin rule;
- Gemini 3.5 Flash with reasoning enabled, reached through the public developer API; the earlier build’s draws ran through Vertex AI, and on an earlier configuration the two surfaces reproduce the same release’s output to within 0.009 on every measure (technical report, Appendix H.12); and
- $n = 300$ and three draws per dataset.

Adult and finance use hand-tuned cohort and conditional hierarchies. NHANES uses the auto-configured release of Algorithm 2: three age cohorts and two conditional levels over age, diastolic blood pressure and race/ethnicity.

Several results were produced on the earlier configuration the method was developed on, and each is labelled where it appears. They are:

- the powered six-draw equivalence test of Section 6.1;
- the 3-way workload table (technical report, Section 7.3);
- the saturation and inversion controls of Section 6.3;
- the transmission sweeps and the over-coupling decomposition of Section 6.4;
- the Diabetes 130 budget sweep of Section 6.5;
- the generator ladder of Section 6.6;
- the cohort-wise and cell-wise comparison of Section 6.8;
- the configuration C and configuration A rows of Table 23 (Section 6.9); and
- the membership-inference evaluation of Section 6.10, except the attacks on the shipped-configuration draws (Appendix C.3).

That configuration differed from the shipped one in four ways. It released pooled rather than class-conditional histograms. It stated the release to the generator as shares rather than exact counts. It kept every returned row rather than selecting from a pool. And, in the six-draw Adult arm, it showed the generator only the four most common values of each categorical attribute. Every one of those differences is conservative for CoRTeC in a fidelity or utility comparison; Section 6.10 states which draws its attacks read. The conclusions those sections draw concern the variable each isolates, not the configuration.

5.6 What the controls rule out before the results

Every real dataset in Table 2 is a public benchmark, and the generators we deploy are closed-weight models whose pretraining corpus we cannot audit. Two objections follow, and the experiments that answer them are stated here, before the results, because a reader who holds either objection will otherwise read every table through it. The first is recitation: that the model reproduces records or marginals it has seen. The second is that the mechanism is a property of one vendor’s model.

Three controls answer the first. A constructed renal registry with no public presence (Section 6.3) keeps CoRTeC’s margin over an ungrounded model unchanged, 0.054 against 0.057 on Adult, a ratio of 0.95, so the margin does not depend on the model having seen the data. An inversion test (Section 6.3) plants a relationship that contradicts the model’s prior, advanced degrees paired with low income, and the output follows the private release, emitting the high-income label for 0.000 of advanced-degree holders where the same model without the release emits it for 0.931; on a second vendor under the current release rule the same test gives 0.000 against 1.000. A matched control gives the model CoRTeC’s own prompt with the released arrays deleted, so that the release, and not the prompt’s wording, is

what the control lacks. The membership-inference attacks of Section 6.10, validated on a positive control, find no private record in the output. What these controls do not rule out is recall of a public benchmark’s marginal distributions, and Section 10 says so.

The open-weight control answers the second. The transmission sweep of Section 6.4 was repeated on nine self-hosted open-weight models spanning six families; every family at or above 20B parameters transmits the planted relationship with a mean error of 0.10 or less (Appendix E). Those models are scientific controls on the mechanism and not a deployment proposal, for the reason Section 6.6 gives: on full-dataset generation their output is close to that of an unconditioned prompt.

6. Results

6.1 Head-to-head: fidelity at the release’s own level, utility at the floor

The bound first. No output decoded from a release can be expected to be closer to the private data than the release itself. At $\epsilon = 2$ with a fifth of the budget on the conditional table, the release’s 1-way total variation against the training data is 0.020 on Adult and 0.013 on finance under the public bins. A 300-record real sample records 0.043 and 0.041 on the same measure. The release therefore carries less marginal error than a sample of the size we generate.

Adult. Table 3 reports three draws from one release beside the baselines at five draws each. CoRTeC’s 1-way error, 0.026, is below the real sample’s 0.043 and within 0.002 of MST’s 0.024; that difference does not survive correction (adjusted $p = 0.16$), so no comparison in this section leaves a baseline’s error significantly lower. Its 2-way error, 0.106, equals the real sample’s 0.107 within noise and is below AIM’s 0.119 and MST’s 0.144. Conditional error over seen groups, 0.017, is a quarter of the real sample’s, because the class-conditional blocks are estimated from all 26,048 training records and a 300-record sample is not. Over held-out groups it is 0.040 against the sample’s 0.036. The three students train at 0.839, 0.875 and 0.844 against the sample’s 0.830, 0.870 and 0.840. The difference from AIM and MST on every student is 0.15 to 0.18 AUC.

Table 3: Adult at $\epsilon = 2$, $n = 300$. The CoRTeC rows are three draws from one release gated under Algorithm 1 (noised, charged counts), decoded with the exact counts stated as totals over the outcomes (Section 4.4).

condition	draws	1-way TV ↓	2-way TV ↓	cond. seen ↓	cond. held-out ↓	TSTR-LR ↑	TSTR-RF ↑	TSTR-GBM ↑
<i>train on all 26,048 real rows (ceiling)</i>	1	0.011	0.028	0.020	0.008	0.860	0.907	0.914
<i>real sample, $n = 300$ (floor)</i>	3	0.043	0.107	0.062	0.036	0.830	0.870	0.840
CoRTeC (Gemini 3.5 Flash)	3	0.026	0.106	0.017	0.040	0.839	0.875	0.844
CoRTeC (Claude Opus 5)	1	0.030	0.110	0.013	0.042	0.838	0.870	0.825
MST	5	0.024	0.144	0.169	0.050	0.690	0.728	0.681
AIM	5	0.037	0.119	0.054	0.101	0.675	0.700	0.691
<i>permuted target (no-information floor)</i>	3	0.041	0.110	0.152	0.102	0.423	0.485	0.482

Finance. Table 4 reports three draws from one release beside MST and PATE-CTGAN on the full 15-column schema, and beside AIM on the reduced 12-column schema. That schema is the only one AIM completes on within three hours; its fit on the full schema exceeded three hours on every attempt, and the cause is localised to the six high-cardinality amount columns. CoRTeC, MST and the floors are re-scored on those 12 columns for that comparison.

The finance result has the same shape as the Adult result. 1-way error, 0.029, is within 0.001 of MST’s 0.028 (the two do not separate) and below the real sample’s. 2-way error, 0.123, is below MST’s 0.230 and above the sample’s 0.099; on the 12-column schema it is 0.108 against AIM’s 0.136. Conditional error is below the sample’s on seen and held-out groups. No student separates from the real-sample floor: the trees train at 0.721 and 0.699 against 0.727 and 0.717 ($p = 0.50$ and 0.16) and logistic regression at 0.689 against 0.695 ($p = 0.26$), where the earlier release had left it 0.015 short. On the 12-column schema CoRTeC’s 1-way error is lower than AIM’s by a factor of 2.2, and its students are higher on every one. It does not separate from MST on 1-way error, the measure MST is built for.

Table 4: Finance at $\epsilon = 2$, $n = 300$. AIM completes only on the 12-column schema, so that block re-scores every arm on those columns. The CoRTeC rows are three draws from one release gated under Algorithm 1 (noised, charged counts), decoded with the exact counts stated as totals over the outcomes (Section 4.4).

condition	draws	1-way TV ↓	2-way TV ↓	cond. seen ↓	cond. held-out ↓	TSTR-LR ↑	TSTR-RF ↑	TSTR-GBM ↑
<i>train on all 24,000 real rows (ceiling)</i>	1	0.009	0.024	0.013	0.008	0.699	0.748	0.747
<i>real sample, n = 300 (floor)</i>	3	0.041	0.099	0.059	0.045	0.695	0.727	0.717
CoRTeC (Gemini 3.5 Flash)	3	0.029	0.123	0.016	0.028	0.689	0.721	0.699
MST	3	0.028	0.230	0.090	0.150	0.580	0.610	0.604
PATE-CTGAN	3	0.209	0.397	0.192	0.138	0.548	0.501	0.515
<i>permuted target (no-information floor)</i>	3	0.040	0.100	0.137	0.059	0.514	0.482	0.481
12-column schema: CoRTeC	3	0.024	0.108	0.016	0.028	0.683	0.723	0.707
12-column schema: AIM	5	0.054	0.136	0.083	0.036	0.578	0.652	0.623
12-column schema: MST	3	0.023	0.216	0.090	0.150	0.591	0.644	0.636
<i>12-column schema: real sample, n = 300</i>	3	0.038	0.090	0.059	0.045	0.682	0.722	0.709

NHANES, auto-configured. Table 5 is the turn-key case: a release the auto-configurator derived with no hand-tuned hierarchy, generated cohort-wise from a $2 \times$ pool, beside MST, AIM and PATE-CTGAN fitted on NHANES at the same ϵ and binning. NHANES is also the one clinical dataset on which AIM completes (58 s to fit), so it carries the healthcare panel of Figure 3.

The release’s 1-way error against the training data is 0.009, and the selected draws’ 1-way error against the release is 0.003 (both under the release’s convention). The marginal result therefore carries over to a release nobody tuned: 1-way error 0.016 against the sample’s 0.034, conditional error over seen groups 0.013 against 0.015, held-out 0.036 against 0.036.

Two things do not carry over, and both are stated. 2-way error is 0.120 against the sample’s 0.081 (Welch $p = 0.004$): with three cohorts and a four-cell table the release names little pairwise structure, and what the selection does not constrain the generator supplies. And every student trains below the floor: logistic regression at 0.738 against 0.773 ($p = 0.32$), the random forest at 0.679 against 0.728 ($p = 0.033$) and gradient boosting at 0.681 against 0.716 ($p = 0.099$). The random forest is the one student on any of the three datasets that separates from a real sample at three draws before correction; on the earlier release of the same configuration it did not (0.732 against 0.728). The linear gap is not in the release, since the release decoded with no model at all trains logistic regression at 0.767. The gap lies in the youngest cohort, whose diabetic class does not clear $n_{\min}$; that cohort therefore keeps a pooled block and the generator’s values below bin resolution (Section 4.5). CoRTeC’s error is lower than all three baselines’ on every measure except conditional error over seen groups, where MST’s 0.004 and AIM’s 0.009 are below CoRTeC’s 0.013 and neither difference survives correction (adjusted $p = 0.20$ and 0.42).

Table 5: NHANES at $\epsilon = 2$, $n = 300$, under a release nobody tuned. The CoRTeC rows are three draws from one release gated under Algorithm 1 (noised, charged counts), decoded with the exact counts stated as totals over the outcomes (Section 4.4).

condition	draws	1-way TV ↓	2-way TV ↓	cond. seen ↓	cond. held-out ↓	TSTR-LR ↑	TSTR-RF ↑	TSTR-GBM ↑
<i>train on all 2,999 real rows (ceiling)</i>	1					0.797	0.763	0.747
<i>real sample, n = 300 (floor)</i>	3	0.034	0.081	0.015	0.036	0.773	0.728	0.716
CoRTeC (Gemini 3.5 Flash, auto-configured)	3	0.016	0.120	0.013	0.036	0.738	0.679	0.681
MST	3	0.024	0.175	0.004	0.128	0.687	0.646	0.664
AIM	3	0.024	0.142	0.009	0.073	0.596	0.650	0.650
PATE-CTGAN	3	0.095	0.187	0.149	0.150	0.598	0.552	0.539
<i>permuted target (no-information floor)</i>	3	0.043	0.093	0.047	0.060	0.493	0.514	0.515




Figure 3: The central comparison on three datasets. Points are means over draws, bars are 95% bootstrap confidence intervals, and the shaded band spans the no-information floor to a real sample of the same size.

The family statistics. Table 6 gives the Welch tests on the per-draw values, Holm-corrected over each seven-metric family of one baseline on one dataset, in the direction that favours CoRTeC. On Adult and finance, 29 of the 35 comparisons survive correction in CoRTeC’s favour and none separates in a baseline’s favour. The six that do not separate are: - the 1-way comparisons against MST on Adult and on finance (both schemas), where the two methods are within 0.002; - conditional error over seen groups against MST on finance, on both schemas; and - held-out conditional error against AIM on the 12-column schema.

On NHANES, 6 of the 21 comparisons survive at three draws against three. Five of them are fidelity measures and one is the gradient-boosting student against PATE-CTGAN (+0.141, adjusted $p = 0.0008$); against MST and AIM no student separates after correction. The other utility differences on NHANES are consistent in direction and do not survive at three draws. The utility ordering there is therefore a corrected result on one student and a signal on the other two.

Table 6: Holm-corrected families. Cells are the difference CoRTeC – baseline with the adjusted p in brackets. Negative error differences and positive AUC differences favour CoRTeC.

family	1-way	2-way	cond. seen	cond. held-out	TSTR-LR	TSTR-RF	TSTR-GBM
Adult, against AIM	-0.011 (0.0007)	-0.013 (0.0011)	-0.036 (0.0002)	-0.061 (0.0013)	+0.164 (<0.0001)	+0.176 (0.0014)	+0.152 (0.012)
Adult, against MST	+0.002 (0.16)	-0.038 (<0.0001)	-0.152 (0.0011)	-0.010 (0.012)	+0.150 (0.0001)	+0.147 (0.0003)	+0.163 (0.0079)
finance, against MST	+0.000 (0.69)	-0.107 (0.0015)	-0.073 (0.065)	-0.122 (0.0007)	+0.109 (0.0007)	+0.112 (0.0023)	+0.095 (0.049)
finance, 12 columns, against AIM	-0.030 (0.0006)	-0.028 (0.0071)	-0.066 (0.0021)	-0.008 (0.49)	+0.104 (0.017)	+0.071 (0.016)	+0.084 (0.01)
finance, 12 columns, against MST	+0.002 (0.49)	-0.108 (0.0021)	-0.073 (0.098)	-0.122 (0.0013)	+0.092 (0.0005)	+0.080 (0.016)	+0.071 (0.03)
NHANES, against MST	-0.008 (0.12)	-0.055 (0.024)	+0.009 (0.2)	-0.092 (0.039)	+0.050 (0.42)	+0.033 (0.1)	+0.017 (0.42)
NHANES, against AIM	-0.008 (0.42)	-0.022 (0.2)	+0.004 (0.42)	-0.037 (0.0081)	+0.141 (0.19)	+0.029 (0.2)	+0.030 (0.42)
NHANES, against PATE-CTGAN	-0.079 (0.025)	-0.067 (0.0095)	-0.136 (0.1)	-0.114 (0.1)	+0.140 (0.42)	+0.127 (0.38)	+0.141 (0.0008)

The powered equivalence test. The claim that a model trained on CoRTeC’s output performs as one trained on a real sample of the same size was first tested with adequate power on Adult. The generator was Claude Fable 5, with six draws against five real samples, on the earlier release design; the prompt showed only the four most common values of each categorical attribute, the weaker of the two prompts we ran. The differences were +0.007, -0.003 and +0.012 AUC on the three students. The 95% confidence intervals on the difference were $[-0.007, +0.021]$, $[-0.015, +0.010]$ and $[-0.000, +0.027]$, and every $p > 0.18$.

A non-significant difference is not by itself evidence of equivalence. What makes this one an equivalence result is that the intervals exclude any advantage or deficit larger than about 0.027 AUC. The same arm regenerated from a fresh release under the two-count rate mechanism of Algorithm 1 reproduces it (0.848, 0.871 and 0.852 against 0.834, 0.872 and 0.843; the one student that moves, moves in CoRTeC’s favour, $p = 0.050$). Tables 3 to 5 remake the result under the shipped configuration and a second generator family on three datasets, at three draws each.

A second vendor. The Adult release was also generated through Claude Opus 5, one complete threefold pool of 900 rows selected exactly as the Gemini pools were. The pool’s 1-way error against the released histograms is 0.007, lower than the Gemini pools’ 0.009 to 0.011. The selected draw reproduces the result (Table 3): each measure is within 0.024 of the Gemini means, and the three students match the real-sample floor. One draw is a check rather than a replication, and we present it as one.

The generative families. All three fail on Adult at $\epsilon = 2$ by not preserving the target’s base rate, in opposite directions: DP-CTGAN collapses towards the negative class (two of three draws contain no positive record, so TSTR is undefined), while PATE-GAN and PATE-CTGAN emit 45 to 60% positives against a real 24.1% (TSTR-LR 0.562 and 0.608). These are library defaults, and the failure is invisible in a marginal-fidelity summary unless the base rate is inspected (technical report, Section 7.2).

AIM’s own workloads. On the metric AIM is built for, 3-way workload error at a sample size adequate for it ($n = 1,950$), AIM records the lowest error on all three workloads, CoRTeC the second lowest, and MST and PATE-CTGAN follow (technical report, Section 7.3). The advantage is structural: AIM’s adaptive selection optimises exactly that workload under the budget, and we did not set out to match it.

Are AIM and MST under-tuned? They run at smartnoise-synth defaults, at matched ϵ and matched discretisation, and on Adult the answer is yes. A sweep of the two settings a practitioner would try first, fitted on the same training split under the same public bins and scored under the same protocol, raises AIM’s junction-tree limit from 80 MB to 300 MB and its workload from 2-way to 3-way marginals (Table 35, Appendix G). The larger model trains logistic regression at 0.772 and the trees at 0.867 and 0.835; the 3-way workload at 0.812, 0.876 and 0.847. Against CoRTeC’s 0.839, 0.875 and 0.844 and the real sample’s 0.830, 0.870 and 0.840, the tree students no longer separate and the linear student is 0.03 short, where the defaults were 0.15 to 0.18 short. Conditional error over seen groups stays at 0.045 and 0.046 against CoRTeC’s 0.017; held-out conditional error falls to 0.029 and 0.026, below CoRTeC’s 0.040; and 2-way error falls to 0.102, below CoRTeC’s 0.106. The cost is fitting time: 30 minutes for the larger model and 13.4 hours for the 3-way workload, against 23 minutes at the defaults. The utility margin of Table 3 is therefore a margin over the library defaults on this dataset, and the claim this paper makes is the narrower one: a release built for a classifier reaches the real-sample floor with no fitting, and a marginal method reaches it on Adult when given a larger model or a richer workload and the hours to fit it. Two other pieces of evidence stand. Section 8.2 shows that giving AIM and MST a DP conditional table moves AIM from 0.675 to 0.777 and MST from 0.690 to 0.773 without any change of configuration, so most of the default margin is in what is released; and the residual is not the language model’s prior (Section 6.3). Whether tuning has the same effect on finance and NHANES, where AIM at defaults fits in under a minute on NHANES and not at all on the full finance schema, we have not measured, and a third setting, both changes together, was still fitting when this version was prepared.

6.2 What the release carries, and what each step of Stage B contributes

The release alone, decoded with no model. The clearest way to see what a release carries is to decode it by independent sampling, with no language model and no prior. A cohort is drawn by its released size, the outcome from the released class balance, and every other column from that outcome’s histogram block. Under a pooled release, the columns come from the cohort’s single block and the outcome from the conditional table. Table 8 does this five times for each release design on finance and on Adult.

Decoded this way, the class-conditional release trains better models than the pooled one on every student and both datasets. The gain is 0.02 to 0.04 AUC on finance (Welch $p = 0.089, 0.048, 0.013$ for LR, RF, GBM) and 0.05 to 0.06 on Adult ($p \leq 0.005$ on all three). The class-conditional release is within 0.011 AUC of the real-sample floor on every finance student and within 0.019 on every Adult student. Held-out conditional error falls by 31 to 39%. The pooled release, decoded the same way, gives the same utility as our earliest generated finance arm did: the information a classifier needs was not in the release the generator was given. The naive decode is not a competitor to the generator, since its 2-way error is $1.6\times$ the real sample’s. It is a lower bound on the information the release contains.

Table 8: Each release design decoded by independent sampling, with no model (five decodes each).

release, decoded naively	1-way TV ↓	2-way TV ↓	cond. seen ↓	cond. held-out ↓	TSTR-LR ↑	TSTR-RF ↑	TSTR-GBM ↑
finance , pooled	0.053	0.157	0.053	0.042	0.666	0.701	0.664
finance , class-conditional	0.054	0.161	0.061	0.029	0.687	0.733	0.706
<i>finance</i> , real sample $n = 300$	<i>0.041</i>	<i>0.099</i>	<i>0.059</i>	<i>0.045</i>	<i>0.695</i>	<i>0.727</i>	<i>0.717</i>
Adult , pooled	0.052	0.144	0.069	0.094	0.752	0.814	0.792
Adult , class-conditional	0.058	0.150	0.070	0.057	0.811	0.861	0.842
<i>Adult</i> , real sample $n = 300$	<i>0.043</i>	<i>0.107</i>	<i>0.062</i>	<i>0.036</i>	<i>0.830</i>	<i>0.870</i>	<i>0.840</i>

The same generator on both releases confirms it. With one finance release of each kind, Gemini 3.5 Flash, the same prompts and three draws per release, the class-conditional release raises every student: +0.029, +0.050 and +0.042 AUC (Welch $p = 0.007, 0.017, 0.029$; Hedges’ g , a standardised effect size, of 2.4 to 4.0). The four fidelity measures stay within draw-to-draw spread ($p \geq 0.20$). The pooled arm under Gemini reproduces the pooled arm under Claude Table 5 to within 0.012 AUC on every student (0.651, 0.662, 0.662 against 0.652, 0.673, 0.664), which is direct confirmation that the ceiling was the release’s, not the generator’s.

Under Claude Table 5 on the same release design the tree students again reach the floor (0.723 and 0.716 against 0.727 and 0.717), but held-out conditional error rises from 0.048 to 0.057 ($p = 0.007$), a cost the Gemini arm does not show. The per-outcome blocks give that generator more to honour per cohort, and the cost appears on the conditional families the release does not name. We report it as a cost of the design under one generator rather than as noise.

Exact counts and selection. The two Stage B steps were separated on the Adult release by scoring the same generated rows before and after selection (Table 9). Exact counts act on the pool: the three generated pools (879, 900 and 900 rows) match the released histograms to 0.009 to 0.011, below the release’s own distance from the truth, whereas the plain share-based prompt’s rows have an error of 0.052 against theirs. But any 300 rows drawn at random from a faithful pool carry the sampling error every 300-record sample carries, and a random 300 rows from that pool have a 1-way error of 0.050, close to the real sample’s 0.043.

Selection removes that sampling error. 1-way error falls from 0.050 to 0.029, 2-way error equals the real sample’s, conditional error falls by almost three quarters, and the three students move up by 0.009 to 0.027 AUC. The two steps are a pair. Counts without selection give a pool the selection can trust; selection without counts chooses from rows that were never asked to match, which produced no gain that survived a significance test on the earlier arms.

Table 9: Exact counts and selection, separated on one Adult release with three pools. The selected row is re-selected from the same three pools at a fixed seed, which is why its 1-way error coincides with the earlier build’s Table 3 row while the students differ slightly; Table 9 is on the earlier release.

condition	1-way TV ↓	2-way TV ↓	cond. seen ↓	cond. held-out ↓	TSTR-LR ↑	TSTR-RF ↑	TSTR-GBM ↑
exact-count batches, a random 300 of each pool	0.050	0.131	0.057	0.052	0.826	0.851	0.821
the same pools, the 300 rows selected to the release	0.029	0.109	0.015	0.037	0.835	0.872	0.848
<i>real sample</i> , $n = 300$	<i>0.043</i>	<i>0.107</i>	<i>0.062</i>	<i>0.036</i>	<i>0.830</i>	<i>0.870</i>	<i>0.840</i>
<i>the release itself against the training data</i> (release convention)	<i>0.020</i>						

The sub-bin rule. Table 10 applies the rule to the current-release and pooled arms, with the values the generator produced beside the values the rule produces. It does what it was built for on the arm that needed it, and nothing on the arms that did not. On the class-conditional arms of Adult and finance the students move by at most 0.010 AUC, in both directions, inside draw-to-draw spread. Two alternatives, a redraw in every cohort and a per-block mean calibration, were measured and rejected (technical report, H.17).

Table 10: The sub-bin rule on the current-release and pooled arms: the generator’s values, then the release’s. The earlier-release arms are in the technical report, H.17.

arm	draws, n	TSTR-LR	TSTR-RF	TSTR-GBM	1-way TV	real sample LR / RF / GBM
NHANES, shipped configuration, current release	3, 300	0.711 to 0.738	0.665 to 0.679	0.663 to 0.681	0.017 to 0.016	0.773 / 0.728 / 0.716
Adult, shipped configuration (Gemini), current release	3, 300	0.837 to 0.839	0.872 to 0.875	0.851 to 0.844	0.023 to 0.026	0.830 / 0.870 / 0.840
Adult, shipped configuration (Opus 5)	1, 300	0.840 to 0.838	0.872 to 0.870	0.833 to 0.825	0.027 to 0.030	0.830 / 0.870 / 0.840
finance, shipped configuration (Gemini), current release	3, 300	0.685 to 0.689	0.715 to 0.721	0.700 to 0.699	0.026 to 0.029	0.695 / 0.727 / 0.717
NHANES, pooled release	1, 600	0.763 to 0.763	0.744 to 0.744	0.733 to 0.733	0.025 to 0.025	0.778 / 0.735 / 0.725
Diabetes 130, pooled release	1, 300	0.555 to 0.555	0.570 to 0.570	0.566 to 0.566	0.053 to 0.053	0.557 / 0.556 / 0.543

6.3 Both standard acceptance criteria are saturated

Marginal fidelity. A common statement of the fidelity goal is that synthetic data should be “at least 90% statistically similar” to the private data, operationalised as $1 - \text{TV}$. Table 11 tests whether that criterion can tell good data from useless data, using the permuted-target control on Adult. The permuted control has no usable feature-to-target relationship (TSTR 0.458, near chance) and yet records 95.7% 1-way similarity, passing a 90% bar, because permuting one column of fifteen leaves every marginal intact. Tightening the bar far enough to exclude the useless case also excludes a genuine sample: on 2-way similarity the pair is 0.106 and 0.112, so a 90% two-way bar rejects both, including real data drawn from the private distribution itself. A criterion that fails real data is not a usable acceptance test.

Table 11: A marginal criterion cannot separate good data from useless data (Adult, $n = 300$; earlier configuration).

metric	real sample (known good)	permuted target (known bad)	separates?
1-way TV	0.042	0.043	no; saturated
2-way TV	0.106	0.112	no; saturated
conditional TV (seen)	0.063	0.155	yes
conditional TV (held-out)	0.036	0.102	yes
TSTR-LR	0.834	0.458	yes

We therefore propose that any fidelity criterion for private synthesis carry a conditional term. A concrete instance, calibrated on Adult at $n = 300$ and offered as an illustration rather than as a standard, that real data and CoRTeC pass, while AIM, MST, PATE-CTGAN, DP-CTGAN, PATE-GAN and the permuted floor all fail, is: $1\text{-way TV} \leq 0.06$, $2\text{-way TV} \leq 0.135$, and $\text{mean conditional TV} \leq 0.07$. The separating work is done by the conditional term. AIM fails it at 0.077, MST at 0.110 and the permuted floor at 0.129, while CoRTeC, the one method that passes, is at 0.029. The marginal thresholds exclude the deep generative baselines, which miss by an order of magnitude, and MST, whose 2-way error of 0.144 is above the bar. The 2-way threshold depends on how pairs are counted: it was 0.12 under a 20-pair sample and is 0.135 over all 105 pairs, for the same data. The conditional term’s scale did not move, which is one more reason to let it carry the criterion.

Aggregate utility. It does not follow that aggregate utility is safe. The header-only control gives the same frozen model nothing but the column names. On Adult it reaches TSTR-LR 0.824, against a real 300-record sample’s 0.834, while AIM reaches 0.675 and MST 0.690. On that dataset, then, an ungrounded language model with no access to the private data at all comes within 0.010 of a real sample and exceeds AIM and MST by 0.13 to 0.15 on the metric the field uses to argue for downstream usefulness. That is a result about the metric and about the datasets: on public benchmarks a pretrained model already encodes most of the aggregate structure, so aggregate utility cannot distinguish a method that reads the private release from one that recites a prior.

Making the prior wrong. We can separate the two by inverting a relationship the prior knows. In the inversion condition the released statistics state that advanced-degree holders (`education_num` ≥ 14) earn over 50K at a rate of 0.2%, against a real-world rate of 61.9%. The control is matched: it takes CoRTeC’s own prompt and strips exactly the released blocks (class balance, histograms, categorical proportions, conditional table, cohort size), leaving every other line byte-identical, and it runs through the same generation routine, so row allocation, batching, parsing and repair are shared by construction.

With one release, Claude Fable 5 and $n = 300$ per condition, CoRTeC emits the high-income label for 0.000 of advanced-degree holders, tracking the release. The matched control emits it for 0.931, more extreme than the real-world prior (Table 12). Since every other element of the two conditions is identical, the separation is attributable to the released statistics alone. The control is told to match a table and to ignore world knowledge; it has no table, and answers from its prior. We report one draw per arm because the measure spans the full $[0, 1]$ range: draw-to-draw variation on conditional quantities in this paper is 0.004 and release-to-release variation is 0.037, more than an order of magnitude below the effect.

Table 12: The inversion test. The two conditions are identical but for the released arrays. The Claude Fable 5 rows are the earlier configuration; the GPT-5 rows are the current release rule.

matched condition	emits the high-income label for advanced degrees
CoRTeC	0.000 , tracking the release
matched header-only control	0.931 , more extreme than the real-world prior
CoRTeC, GPT-5 at low reasoning, release under the current rule	0.000 , tracking the release
CoRTeC, GPT-5 at minimal reasoning, same release	0.276
matched header-only control, GPT-5 at minimal reasoning, same release	1.000
<i>real data, uninverted</i>	<i>0.619</i>

On a second vendor, under the current release rule. The test was repeated on GPT-5 with one fresh inverted release made under the $n_{\min}$ rule of Algorithm 1, so the release carries pure $\varepsilon = 2$, and the same three conditions. With reasoning at GPT-5’s low level CoRTeC emits the high-income label for 0.000 of 24 advanced-degree holders, and every education band is within 0.07 of its released rate (0.119, 0.217 and 0.490 against released 0.129, 0.206 and 0.416). The matched control emits it for 1.000 of 52. At minimal reasoning CoRTeC emits it for 0.276 of 29, and over-emits the positive class in every band, by 0.13 to 0.26, while keeping graduates lowest: the inverted ordering transmits and the magnitudes do not, which is the reasoning effect of Section 6.6 on the hardest case. The minimal-reasoning control also returned only the CSV header, with no rows, on 4 of 22 calls; the generator’s parse guard caught each one, and the raw text is now kept whenever it does.

Evaluated on a held-out test set carrying the same inverted relationship, the model trained on header-only output is wrong for 72% of the inverted subgroup. Its aggregate AUC still exceeds CoRTeC’s (0.730 against 0.670), because the subgroup is 7.9% of rows and the aggregate is dominated by the 92% where the prior is correct.

On the uninverted release the same matched control separates too, at two independent replications of the whole pipeline. CoRTeC’s TSTR-LR is 0.057 higher than the control’s (0.849 against 0.792) against a pooled draw-to-draw spread of 0.001, and its conditional error is $3.7\times$ lower (0.043 against 0.160). The control reaches 0.845 TSTR-GBM where a real 300-row sample reaches 0.840: an ungrounded model exceeds real data of the same size on that student. That is the saturation this section exists to demonstrate, and it survives the prompts being matched.

A contamination control on data with no public presence. Every dataset above is a public benchmark the frozen generator has very likely seen in pretraining. So we constructed a dataset with no public presence: a renal-replacement-therapy registry of 20,000 records whose joint distribution is defined by a generative process in our own code. It has a plausible clinical schema and one deliberately counter-intuitive driver: mode of transport to dialysis outranks every clinical variable as a predictor of hospitalisation. The auto-configurator, given only the schema, independently selected `patient_age` and `transport_mode`.

We generated CoRTeC and the matched header-only control from the same schema (Gemini 3.5 Flash, $n = 1,000$, two draws each). CoRTeC records 1-way TV 0.080 and TSTR-LR 0.685, against the control’s 0.541 and 0.630 and a real sample’s 0.019 and 0.693. Header-only could not reproduce the schema at all: it invented 33 levels across the four categorical columns, and 99.2% of its categorical values are absent from the real data.

The diagnostic this control specifies is whether the CoRTeC-to-header-only gap changes on data with no public presence. Against the matched control it does not: 0.057 on Adult and 0.054 here, a ratio of 0.95. CoRTeC’s margin over an ungrounded model does not shrink when the prior is removed. What the prior supplied on Adult is visible in the control’s fidelity (1-way error 0.102 on Adult against 0.541 here), not in CoRTeC’s margin. CoRTeC’s own marginal error here, 1-way TV 0.080 against a real sample’s 0.019, is above the real sample’s where on the three head-to-head datasets it is below; that arm is the earlier configuration at $n = 1,000$, without exact counts or selection, and we have not run the shipped configuration on the registry.

This also answers the objection that the architecture leans on the model’s prior and would be a liability on idiosyncratic enterprise data. The prior supplies fluency in the schema, plausible values and correct types, and CoRTeC relies on that fluency; the release supplies the structure. When the prior is weak, only the release can supply it. A constructed dataset is not a real private extract, and an institutional extract remains the experiment we have not run.

6.4 Transmission: which mechanisms carry a private relationship

A generator built on a language model invites one specific doubt no aggregate metric can settle: perhaps its output is good because the model’s prior about census or clinical data happens to be right, not because it read the released statistics. We test it directly.

Definition 4 (Transmission of a private relationship). Fix a group g and a schedule of target rates $r_p, \dots, r_T$. For each r_p construct $D^{(t)}$ by resampling y within g at rate r_p , run the mechanism on $D^{(t)}$, and let $g^{(t)}$ be the realised rate of $y = 1$ within g in the synthetic output. Transmission is the pair

$$\beta = \text{slope of } g^{(t)} \text{ on } r_p, \text{MAE} = \frac{1}{T} \sum_t |g^{(t)} - r_p|, \quad (5)$$

where r_p is the rate the mechanism was given: the released rate for a mechanism that reads a release, and the realised rate in the forced data for one fitted directly.

$\beta = 1$ with $\text{MAE} = 0$ is faithful transmission; $\beta = 0$ means the output is independent of the private data. Both must be reported, since a generator exact at the endpoints and wrong in between records $\beta \approx 1$ with a large MAE.

Table 13 shows that CoRTeC transmits, across three domains, with Stage A re-released from the modified data at every point. On NHANES the released rates were 0.008 / 0.469 / 0.970 and CoRTeC produced 0.0% / 44.6% / 100.0% over 60 to 65 rows per point. The unconditioned control is the comparison that matters in the table: it emits the same number at every target, 98.5% on hospital data against a true rate of 21.4%. CoRTeC’s output therefore tracks the released statistics rather than the model’s prior. No amount of downstream AUC reveals this, because AUC is rank-based and the direction is right, which is a concrete reason a readmission probability or a default rate must be validated on a conditional measure.

Table 13: Transmission of a forced relationship through CoRTeC. The unconditioned control emits the same number at every target. Every row but the GPT-5 one is the earlier configuration.

domain	relationship forced	slope	MAE	unconditioned control	true rate
census (Adult)	education to income	1.063 [0.973, 1.168]; 3 seeds, 14 points	0.055	88.3%	61.9%
census (Adult), GPT-5 at minimal reasoning, releases under the current rule	education to income	0.992; 1 seed, 5 points	0.104	not run	61.9%
healthcare (Diabetes 130)	prior admissions to 30-day readmission	0.995	0.009	98.5%	21.4%
finance (credit)	repayment status to default	0.962 / 1.010; 2 seeds	0.019 / 0.023	100.0%	69.6%
healthcare (NHANES), auto-configured	race/ethnicity to diabetes	1.041	0.020	63.9%	15.4%

A one-seed repeat of the Adult sweep on GPT-5 at minimal reasoning, with every release made under the current rule, records slope 0.992 and MAE 0.104 (Table 13): the direction transmits and the interior magnitudes are pulled towards the prior, which is why Definition 4 reports both numbers; with reasoning on, the inversion test above transmits exactly.

The same test on the deployed mechanisms. We ran the identical protocol on the baselines: force the rate in the private data, fit at $\epsilon = 2$ on the modified data, sample, and measure. The group is defined by public bin membership, so every mechanism can represent it. Table 14 and Figure 7 give the result, and it is not the separation we expected.

MST transmits this relationship as accurately as CoRTeC does, and the reason is structural. The manipulated quantity is a two-way marginal; MST selects and privately measures two-way marginals, and forcing the rate to an extreme makes that marginal more salient to its selection step. PATE-CTGAN does not transmit it at all. Its raw output spans

only 0.079 across a target range of 1.0, the same qualitative behaviour as an unconditioned generator, reached by a different route: DP-SGD and PATE inject noise into the training signal, and at $\epsilon = 2$ on a 19-attribute schema the conditional structure does not survive it.

Table 14: Transmission by mechanism family, on identical private data at identical $\epsilon = 2$ (earlier configuration).

method	family	slope	MAE	output at 0% / 50% / 100%
MST (Diabetes 130)	marginal / graphical	0.998	0.001	0.002 / 0.506 / 1.000
CoRTeC (Diabetes 130, Claude Fable 5)	released statistics + frozen model	0.995	0.009	0.000 / 0.520 / 0.986
PATE-CTGAN (Diabetes 130)	PATE-trained generative	0.054	0.376	0.348 / 0.324 / 0.402
MST (NHANES)	marginal / graphical	0.946	0.021	0.054 / 0.500 / 1.000
CoRTeC (NHANES, Gemini 3.5 Flash)	released statistics + frozen model	1.041	0.020	0.000 / 0.446 / 1.000
PATE-CTGAN (NHANES)	PATE-trained generative	0.095	0.388	0.241 / 0.232 / 0.336




Figure 7: One forced relationship on NHANES (race/ethnicity to diabetes), three mechanisms. MST and CoRTeC track the diagonal; PATE-CTGAN's output is very nearly flat.

Three conclusions follow.

- Whether a private conditional relationship survives depends on the mechanism family, not on whether a method carries a privacy guarantee. Two methods here are equally $\epsilon = 2$ differentially private, and one reproduces the relationship to within 0.001 while the other is effectively blind to it. A practitioner selecting on published fidelity numbers, or on the presence of a guarantee, has no way to see the distinction.
- The test establishes the narrower thing it was designed for: that CoRTeC's output is driven by the released statistics.
- The utility gap of Section 6.1 cannot be explained by an inability to carry a conditional relationship. MST carries this one essentially perfectly on Diabetes 130 and with slope 0.946 on NHANES, where its random-forest student is still 0.082 AUC below a real sample's (Table 5); the 0.15 AUC gap of Section 6.1 is Adult's, where the protocol was not run.

What the marginal methods lose. Ruling that out leaves the harder question of what they do lose. Table 15 decomposes each synthetic set's departure from real data into retention of the feature-to-target association $I(X;Y)$ and of pairwise feature dependence $I(X;X)$. Each is relative to the mean over 25 real samples at the same n , so that the plug-in estimator's small-sample bias cancels; the real-sample control scores 1.02 and 0.97, as it must.

Two distinct failure modes appear. MST and AIM inflate pairwise feature dependence by factors of 2.8 and 2.2 against a real sample of the same size, where CoRTeC inflates it by 1.24. A graphical model fitted to a set of privately measured marginals imposes exactly the dependence structure those marginals imply, and at $\epsilon = 2$ on a 15-attribute schema that structure is coarser and more strongly coupled than the data's own. A downstream model trained on over-coupled records learns dependencies that do not hold on real test data. AIM is the instructive case: it retains the feature-to-target association almost exactly (0.98) while training models 0.17 AUC lower, so the loss cannot be attributed to the target relationship. PATE-CTGAN fails differently, retaining 37% of the association with a decision rule nearly orthogonal to the real one.

CoRTeC’s own distortion is of a different kind. It over-couples the features to the target (1.74 against 1.02), because the generator reproduces the released conditional dependence at least as sharply as the release states it. That is a calibration error a downstream user can see and correct on real held-out data, whereas over-coupled features are learned as dependencies that do not exist. It is still a real distortion, and a deployment that consumes calibrated probabilities should recalibrate before use. Across all 29 draws of seven conditions, TSTR correlates with conditional fidelity at $r = -0.64$ to -0.70 and with marginal fidelity at $|r| \leq 0.16$.

Table 15: Two failure modes (Adult, $n = 300$, earlier CoRTeC configuration). Retention is relative to a real sample of the same size.

method	$I(X;Y)$ retention	$I(X;X)$ retention	rule cosine	positive rate
<i>real sample (control)</i>	1.02	0.97	0.46	0.241
CoRTeC (Claude Fable 5)	1.74	1.24	0.35	0.249
AIM	0.98	2.15	0.35	0.243
MST	2.12	2.83	0.31	0.237
PATE-CTGAN	0.37	2.01	0.04	0.447

6.5 The privacy budget

Table 16 gives the sweep on NHANES under the shipped configuration, one draw at each of $\epsilon = 0.3$, 1 and 8 beside the earlier release’s three draws at $\epsilon = 2$, with MST refitted at each budget. On this dataset the budget matters. NHANES has 2,999 training records, and its auto-configured release spends each cohort’s budget over ten queries and two outcome classes. At $\epsilon = 0.3$ the per-query budget is therefore 0.024, and the Laplace scale on a histogram bin is 42 records inside cohorts of 314 to 1,900. On the earlier release, CoRTeC’s utility falls from 0.752 at $\epsilon = 2$ to 0.731 at $\epsilon = 1$ and 0.570 at $\epsilon = 0.3$, and its 1-way error rises from 0.015 to 0.063. MST degrades in the same way (0.687 to 0.587 on TSTR-LR). Between $\epsilon = 2$ and $\epsilon = 8$ the linear student and 1-way error do not move; the two tree students read 0.033 and 0.034 lower at $\epsilon = 8$, on one draw, with no spread measured at that budget.

Table 16: The privacy-utility curve on NHANES, $n = 300$, on the earlier release. References at this n : real-sample floor 1-way 0.034, conditional-seen 0.015, TSTR-LR 0.773; permuted-target floor 0.043 / 0.047 / 0.493.

metric	method	$\epsilon = 0.3$	$\epsilon = 1$	$\epsilon = 2$	$\epsilon = 8$
1-way TV ↓	CoRTeC	0.063	0.034	0.015	0.013
	MST	0.046	0.029	0.024	0.021
cond. TV (seen) ↓	CoRTeC	0.034	0.024	0.006	0.005
	MST	0.056	0.023	0.004	0.004
cond. TV (held-out) ↓	CoRTeC	0.045	0.027	0.036	0.035
	MST	0.116	0.143	0.128	0.137
TSTR-LR ↑	CoRTeC	0.570	0.731	0.752	0.770
	MST	0.587	0.632	0.687	0.692
TSTR-RF ↑	CoRTeC	0.606	0.729	0.732	0.699
	MST	0.575	0.628	0.646	0.668
TSTR-GBM ↑	CoRTeC	0.600	0.712	0.711	0.677
	MST	0.503	0.633	0.664	0.679

On a large dataset the curve is flat. On Diabetes 130, with 81,410 training records and the earlier configuration, CoRTeC at $\epsilon = 0.3$ is as good as at $\epsilon = 8$ on every metric except conditional error over seen groups, which degrades from 0.009 to 0.019, still better than a real 300-record sample’s 0.031. MST records lower 1-way error at every budget, by roughly 2.7×. CoRTeC’s 2-way error is lower at every budget, and its conditional error is lower by 2.2 to 7.6×. Aggregate TSTR does not separate the two at any ϵ ; both are in the range 0.54 to 0.57 against a floor of 0.557, because 30-day readmission is weakly separable. The release itself degrades gracefully there, and structurally: a histogram’s sensitivity is 1 at every budget, and the release carries zero impossible standard-deviation values at any ϵ (technical report, H.2). On a small dataset the release, not the generator, binds at tight budgets, and its noise-to-signal ratio is computable from the release alone before any generator runs.

6.6 The generator

The architecture is defined by what it releases, but its output quality depends on the frozen model placed in Stage B, and that dependence is large. The technical report (Section 7.5) measures it on Adult with full-dataset generation from one release under the earlier configuration, across nine generator configurations, so the only variable is the generator.

Gemini 3.1 Pro, GPT-5, Claude Opus 5 and Claude Fable 5 fall in a band of 0.041 to 0.046 on conditional error, across three independent pretraining corpora, and every one is below what a real 300-record sample achieves (0.062). That is also the strongest available cross-corpus evidence on contamination: three separately trained models cannot have memorised Adult identically, and all track an inversion that contradicts it (technical report, Section 7.5). Welch tests between the two Anthropic frontier models find no significant difference on any of the seven metrics (smallest $p = 0.076$). The lower block spans two vendors and three size tiers, and its common feature is that reasoning was suppressed or absent.

The controlled demonstration is GPT-5 against itself: same release, same prompts, one flag changed (Table 19). Enabling reasoning improves conditional fidelity 3.8 $\times$. The two arms are 0.128 apart on conditional error, against standard deviations of 0.032 and 0.007. Downstream utility does not resolve the difference at any feasible draw count. The direction is consistent across all three students, but resolving even the most favourable of the gaps at 80% power would take 18 draws per arm, and the least favourable 112.

The finding is that this measure cannot detect the difference. A practitioner choosing between these configurations on downstream utility would see two indistinguishable options and deploy the one that is 14.8 $\times$ cheaper. They would have chosen output whose conditional structure is worse than a no-information control while it still records 95% of a real sample’s downstream AUC. Output headroom is the obvious confound, and it contributes nothing: tripling Sonnet 5’s output budget at fixed effort changes output per call not at all, and raising effort at fixed budget is the only step that moves the fidelity measures.

Table 19: One flag. Both arms use one byte-identical release and identical token limits (earlier configuration).

GPT-5 configuration	draws	1-way TV $\downarrow$	cond. seen $\downarrow$	TSTR-LR $\uparrow$	thinking tokens	cost per draw
reasoning_effort = minimal	3	0.109 $\pm$ 0.003	0.173 $\pm$ 0.032	0.786 $\pm$ 0.050	0	\$0.19
default	3	0.040 $\pm$ 0.001	0.045 $\pm$ 0.007	0.802 $\pm$ 0.025	261k (94% of output)	\$2.81

Reasoning does not substitute for capability in either direction. Claude Sonnet 5 with reasoning verifiably firing on 34 of 34 calls reaches 0.128: a real improvement on its suppressed 0.154, but nearly three times the frontier band and only modestly clear of the no-information floor. Claude Opus 5 reaches 0.046 with reasoning verifiably off. What the band has in common is frontier-class capability. Reasoning produces a large within-model gain that a weaker model cannot convert into frontier output.

A second vendor on the shipped configuration. The shipped configuration was re-generated through GPT-5 on finance and NHANES, three draws each from the Gemini arm’s earlier release file, so the generator is the only variable (Table 34, Appendix F). The budget forced GPT-5’s minimal reasoning level, at \$0.25 per NHANES draw and \$0.57 per finance draw against \$2.70 per NHANES draw with reasoning on, so the comparison is a vendor change and a reasoning change at once. On finance the result replicates: no measure separates the two vendors after correction, the random forest is 0.021 lower at a Holm-adjusted p of 0.22, and against the real-sample floor the only comparison near significance is the random forest, 0.016 short at an adjusted p of 0.053. On NHANES utility replicates and conditional fidelity does not: no student separates (adjusted p of 0.78 or above), but conditional error over seen groups is 0.038 against Gemini’s 0.006 ($p = 0.0055$, adjusted 0.072) and 1-way error 0.031 against 0.015. That is the direction the reasoning result of Table 19 predicts. The selected minimal-reasoning draws carry 0.100 to 0.110 positives against the release’s 0.138, where the Gemini draws carry 0.137: the pools match the release exactly in both cases, because the quota forces it, and the selection prefers GPT-5’s negatives. One NHANES draw at GPT-5’s low reasoning level, \$2.70 for a pool that stopped at 572 of 600 rows and was selected offline, returns the conditional error to 0.011 and the positive rate to 0.130, with 2-way error 0.104, the lowest of any arm, while its tree students train lower, 0.664 and 0.640. One draw is a signal and is reported as one. The replication the result still needs is three reasoning-on draws under a second vendor.

An open-weight generator. The same releases were decoded through OpenAI’s open-weight gpt-oss-120b (Apache-2.0), served locally through Ollama on one 80 GB GPU at its low reasoning level, so the generator is again the only variable. The arm stands in for a model an institution hosts itself, which is the deployment the architecture

allows; it is not a recommendation of open weights, and the model is unmeasured by the tool’s capability gate. On NHANES the open-weight generator trains the three students at 0.685 against 0.773, 0.660 against 0.728, 0.628 against 0.716 (no student separates from the real sample after correction), and no measure separates it from the Gemini arm on the same release; its 1-way error is 0.020 against the real sample’s 0.034 and the Gemini arm’s 0.016. On finance the open-weight generator trains the three students at 0.677 against 0.695, 0.730 against 0.727, 0.701 against 0.717 at one draw, a point value with no test; its 1-way error is 0.060 against the real sample’s 0.041 and the Gemini arm’s 0.029. Generation costs no API fee; a 25-row call took one to three minutes on the shared GPU.

The counts stated per outcome. The open-weight gap was traced to a specification the prompt had left to the model: with per-bin counts stated as totals over the two outcomes, neither generator matched the positives’ class block (mean 1-way distance 0.090 under Gemini, 0.175 under gpt-oss), and selection kept fewer positives from the open-weight pool. Stating the counts per outcome, now the default, puts every generator’s pool at the same distance from the class blocks (0.009 to 0.011 on positives). Decoded again under that prompt, no measure separates gpt-oss from Gemini, nor either from its own totals-only arm, after Holm correction at three draws; the remaining point difference (random forest 0.637 against 0.678) is the model’s, not the specification’s, and is below what three draws resolve (Table 34, Appendix F). GPT-5 at medium reasoning under the same prompt (three draws) trains the students at 0.736, 0.696 and 0.682. On finance one GPT-5 draw under the per-outcome prompt trains the students at 0.697, 0.735 and 0.713 against the real sample’s 0.695, 0.727 and 0.717; the other finance arms were generated under the totals-only prompt, so no comparison is made.

The practical guidance is:

- select a frontier-class model;
- enable reasoning, and verify that it fired from evidence that survives the transport rather than from a setting (Section 9);
- verify the output on a conditional criterion rather than on aggregate utility; and
- re-verify after any change to the generator or its configuration.

Open-weight models measured as controls transmit a forced relationship at every family we tested above 20B parameters. But on full-dataset generation a self-hosted 70B model’s output is close to indistinguishable from an unconditioned prompt on the metrics this method exists to improve. That is why the deployment proposal names enterprise platforms.

6.7 Auto-configuration

Table 20 compares the auto-configured release against expert hand-tuning where a comparator exists, as a release-ceiling comparison at $n = 2,000$. That comparison uses real features with the target redrawn from each cell’s released rate, so it isolates the configuration and not the generator. Auto-configuration is within ± 0.013 of hand-tuning everywhere and better on one dataset. On credit it selects `PAY_0`, `PAY_3` and `PAY_2`, the payment-history columns hand-tuning had missed and which we had independently diagnosed as a cause of that dataset’s early utility gap.

Table 20: Auto-configuration against expert hand-tuning, as a release-ceiling AUC at $n = 2,000$.

dataset	no conditioning	hand-tuned	auto-configured	real target	delta
Adult	0.655	0.825	0.812	0.858	−0.013
Diabetes 130	0.488	0.595	0.607	0.624	+0.012
credit	0.502	0.682	0.677	0.702	−0.005

It generalises to datasets it has never seen. On six additional regulated benchmarks, three health and three finance, each declaring only what a deploying institution would know without looking at its own data, the adaptive selection budget configures every one. It captures 19 to 89% of the achievable range: heart disease 68%, cervical cancer 35%, retinopathy 50%, German credit 19%, Australian credit 86% and bank marketing 89%. A fixed 5% budget declines to configure three of the six, and on one silently produces a configuration worse than not conditioning at all.

On NHANES the rule captures 87%, within two points of the best share on any dataset we tested. The columns it selected there, age, diastolic blood pressure and race/ethnicity, are genuine diabetes risk factors chosen without being told the domain, and Table 5 is generated from that release. The result holds through to generation on a second clinical dataset. On Diabetes 130 an auto-configured release generated through Gemini 3.5 Flash trains the three

students at 0.609, 0.597 and 0.591; the hand-tuned release gives 0.578, 0.583 and 0.563, and a real sample of the same size 0.607, 0.587 and 0.567. The clinical result there therefore holds under a configuration no human chose, on a dataset whose floor-to-ceiling range is narrow (Section 6.5).

6.8 Cohort-wise or cell-wise: a representativeness failure no metric reports

Stage B can generate per cohort, as Algorithm 3 does, or per released conditional cell with an exact positive count, which expresses each cell's rate to within one row. On a constructed registry the cell-wise path reduced conditional rate error 77×, and we shipped it as the default on that basis. On real data it failed in a way that matters more than the metric it was chosen to improve.

On the same release for each dataset, byte-identical by checksum, the cell-wise path is mildly better on Adult and never worse (technical report, Section 7.10). On NHANES it fails, and the failure is not visible in any aggregate number a practitioner checks: aggregate utility reads within 0.02 of the cohort-wise path (0.752 against 0.768), while 1-way error quadruples (0.029 to 0.123) and 2-way error doubles (0.131 to 0.260).

The cause is that cell-wise generation emits rows only for released cells, so population the release does not cover is generated at rate zero. NHANES released four conditional cells, all inside a single diastolic-blood-pressure band and a single coarsened race/ethnicity group (the one holding the White and Black non-Hispanic categories), covering 25.4% of the population; Adult's release covered 99.9%. The technical report (Section 7.10) tabulates the consequence. Four of six race/ethnicity groups, 40% of the population, are absent from the output entirely, along with every record in the 50 to 60 age band. The cohort-wise path reproduces all six groups to within 0.016 on the same release, five of the six within 0.01.

A deployment that shipped this would hold a synthetic cohort with no Asian, Mexican-American, other-Hispanic or multiracial records at all while every fidelity and utility check passed. The conditional criterion does not catch it either, because conditional error is computed over released cells, and those are precisely the cells that are present. The model is not distorting shape within bands; it is simply never asked for the missing cells. Nothing in our own evaluation suite flagged it, and it was found by inspecting per-column output against the release.

The fix is a per-column coverage guard, and it is free. A conditioning column is damaged precisely when the released cells fail to span it, and is otherwise untouched. Coverage is computable from marginals already in the release, so checking it is post-processing. The floor is 90% of each conditioning column's own released mass, placed between the highest failing measurement (0.858) and the lowest passing one (0.911) across eleven per-column measurements on two datasets. An aggregate release-level rule was tried first and fails in both directions.

Below the floor the research pipeline falls back to cohort-wise generation and says so. The shipped tool refuses outright, names the safe alternative and the knobs that change coverage, and names the columns the released cells fail to span. The cohort-wise path is the default of Algorithm 3 for this reason, and it avoids the underlying trade-off. On the NHANES release above, a coarser cell-wise release with full coverage matched the cohort-wise path's marginal fidelity, but was worse than the permuted-target floor on held-out conditional structure (0.055 against 0.053). The cohort-wise path on the richer release reached the real-sample floor on the two tree students at $n = 600$ and came within 0.026 on the linear one (0.752, 0.738, 0.735 against 0.778, 0.735, 0.725), with every group and age band present.

A second mechanism, which the guard cannot see, appeared on Diabetes 130: a conditioning column coarsened into opaque groups was pinned by group membership with the within-group distribution withheld, and the model spread each group uniformly, so the dominant discharge code (59.2% of records) came out at 14.3% while the column's coverage scored 100%. Supplying the within-group shares, a free renormalisation of proportions already in the release, reduced the column's error 10.7×; both implementations ship it (technical report, H.7).

We present the guard as a heuristic mitigation rather than a solved component. It answers which bands of a conditioning column the released cells span, and not what the distribution is inside a band the cells did span. Establishing when a private conditional table can be conveyed to a language model without silent loss is, in our view, an open problem for this line of work. Ganey et al. [17] showed that differential privacy itself has a disparate impact on the minority subgroups of synthetic data. What we observe here is a different mechanism with the same victims: a generation path rather than the noise deletes them, and it is invisible to the same dashboards. The lesson we take is that a representativeness check over the declared schema's categories, against the release rather than against the output alone, belongs in the standard battery.

6.9 Stage C on the primary clinical dataset

Table 23 reports Stage C on the auto-configured NHANES release under the rule Algorithm 5 now ships, scored on the cells each release published. The first three rows are the shipped-configuration draws of Table 5 on the current release, one unseeded bound each, and the fourth pools them; the next four are the same configuration’s earlier release, the draws the earlier build reported, under the same rule; the last two are the earlier configurations C and A of Section 5.5 on their own release, which the coverage guard of Section 6.8 refuses for A. An earlier version of this table labelled configuration C the shipped default, which it is not, and read every row at a fixed tolerance of 0.15 chosen by repetition on this dataset; the last column keeps that reading for comparison.

Table 23: Stage C on NHANES under the shipped rule: the tolerance derived from each release (0.107 for the current release of the shipped configuration, 0.088 for its earlier release, 0.091 for the earlier configurations’ release), and no verdict while a released cell holds fewer than 20 synthetic rows. One unseeded draw per row.

condition	n	thin	worst-case bound	ceiling	floor	verdict under the shipped rule	at $\tau = 0.15$
shipped configuration, current release, draw 0	300	2	0.1520	0.0821	0.1784	none: 2 thin cells	outside
shipped configuration, current release, draw 1	300	3	0.0759	0.0841	0.1699	none: 3 thin cells	within
shipped configuration, current release, draw 2	300	3	0.1400	0.0701	0.1748	none: 3 thin cells	within
shipped configuration, current release, three draws pooled	900	0	0.0874	0.0884	0.1394	within bound ($\tau = 0.107$)	within, and so is the floor
shipped configuration, earlier release, draw 0	300	2	0.1658	0.0763	0.1828	none: 2 thin cells	outside
shipped configuration, earlier release, draw 1	300	3	0.1645	0.0687	0.1745	none: 3 thin cells	outside
shipped configuration, earlier release, draw 2	300	2	0.1291	0.0755	0.1788	none: 2 thin cells	within
shipped configuration, earlier release, three draws pooled	900	0	0.1287	0.0880	0.1302	none: the ceiling fails 0.088	within, and so is the floor
configuration C (earlier; cohort-wise, rate prompt)	600	0	0.3294	0.0662	0.2199	outside, by 0.24	outside
configuration A (earlier; cell-wise, refused by the guard)	600	0	0.0924	0.0723	0.2300	outside, by 0.001	within

Under the shipped rule no single draw of the shipped configuration receives a verdict, on either release, and we state why rather than report the failures and the passes the earlier operating point gave. At $n = 300$ two or three of the four released cells hold fewer than 20 synthetic rows, and in every draw the worst cell is the same one, the 50 to 60-year band, holding 13, 12 and 11 rows on the current release and 9, 9 and 14 on the earlier one: one positive among 13 is a rate of 0.077 against a released 0.185, and (4) carries no sampling term for it, so a verdict there would be a property of a dozen rows. Pooling the draws removes every thin cell. On the current release the pooled table is within the bound: its worst-case bound of 0.087 lies under the derived tolerance of 0.107, the real-sample ceiling clears that tolerance at 0.088 and the permuted floor does not at 0.139, so the controls discriminate and the verdict holds at 95% simultaneous confidence over the four cells. On the earlier release the same pooling gave no verdict, because its derived tolerance of 0.088, halfway between the noise term of 0.029 and the floor’s limit of 0.147, is one the real-sample ceiling itself failed, at 0.088. The difference lies in the release, not in the generator: the current release’s cell rates spread 0.155 from its base rate of 0.155, one cell rate having been clipped to zero by the noise, where the earlier release’s lay within 0.117 of its base rate of 0.138, and the tolerance rises with that spread. On a release whose cell rates lie close to its base rate Stage C at these sample sizes has little power, and the rule says so instead of a verdict. Both earlier-configuration arms are outside their release’s derived tolerance of 0.091: configuration C by 0.24 and configuration A by 0.001, where the earlier operating point had read A as within.

Configuration C fails for a reason the contrast shows. Its worst cell is the same band, where 24 of 48 synthetic rows are positive against a private rate of 0.197: cohort-wise generation under the rate-based prompt pinned each cohort’s marginals and showed the model the conditional table, but nothing forced the rate inside a fine cell to match it. The shipped configuration’s exact-count batches and selection reduce that cell’s gap to between 0.05 and 0.12 over three draws on the current release (0.10 to 0.14 on the earlier one). Table 5’s conditional error over seen groups, 0.006, is not the quantity bounded here: it is a mean over the three stratification bands, where Stage C takes a worst case over the four finest cells, so the two are not reconciled by averaging. The budget must be large enough for the bound’s own ceiling to pass: at $\epsilon_{\text{cert}} = 0.5$ the NHANES ceiling cleared in 21 of 40 repetitions, at 1.0 in 25 of 25 (technical report, H.6).

Under the shipped rule no NHANES run in this paper clears the bound, so the claim the procedure is built to issue is not issued here. Where it is issued it reads: with probability at least 95%, simultaneously over the released cells, which cover 25.4% of the population here, the private and synthetic conditional rates differ by at most the stated bound. The Stage C cost is $\epsilon = 1.0$ on top of $\epsilon = 2.0$ for the release, for $\epsilon = 3.0$ per row and, on this one-row-per-person dataset, per person.

6.10 Membership inference

Theorem 1 already bounds any membership adversary at $\epsilon = 2$ to an advantage of 0.762 by (2). An empirical attack cannot improve on that and cannot validate it. We run one for three reasons the proof does not cover.

- It tests the implementation rather than the mechanism. A suppression threshold not applied, a cohort of one, or a released histogram that is a delta on a single individual would each leave the theorem true and the released data leaky.
- A measured number is what security reviewers ask for.
- For a method built on a proprietary pretrained model, it is the one available answer to the objection that a private record might be memorised and reproduced. We cannot audit weights we did not train, but we can attack the artefact the method publishes, which is where such a record would have to surface to cause harm.

Setup. The standard membership game [40], in the form Stadler et al. [41] apply to synthetic data. The adversary sees the synthetic dataset and decides whether a candidate record was in the private training set. The game runs over 1,000 members from the training split and 1,000 non-members from the held-out split, disjoint and identically distributed, so the attack cannot succeed merely by recognising the data distribution. We run four attacks of increasing strength:

- nearest-neighbour distance;
- exact and near-duplicate matching;
- a discriminative shadow model trained to recognise the synthetic distribution; and
- a per-record likelihood-ratio test in the style of Carlini et al. [8]: sixteen bootstrap density models over a projection, each candidate scored by its mean log-density across shadows divided by its standard deviation, so a record the synthetic data encodes unusually consistently scores high.

Every attack is validated on a positive control, real training records passed off as synthetic, because a null from a blind attack is worthless.

Table 25: Four attacks on four datasets, with a positive control on each. The attacked draws are the earlier-configuration arms of Section 5.5; all four attacks were also run on shipped-configuration draws (Appendix C.3). The positive control detects copying and does not calibrate the attacks against subtler leakage. The permitted advantage of bound (2) is for pure ϵ ; the attacked arms' (ϵ_L, δ) label with $\delta = 1.5 \times 10^{-7}$ moves it by less than 10^{-6} .

dataset	strongest advantage	exact matches	attack AUC	Youden's J	TPR at FPR 0.1%
census (Adult)	0.034	0	0.501	+0.000	0.001
healthcare (Diabetes 130)	0.017	0	0.493	−0.007	0.001
healthcare (NHANES)	0.048	0	0.524	+0.040	0.000
finance (credit)	0.046	0	0.504	+0.016	0.002
<i>chance</i>	0		0.500	0.000	0.001
<i>bound permitted at $\epsilon = 2$</i>	0.762				
<i>positive control (leaking)</i>	0.191–0.250		0.595–0.761	+0.134–0.390	0.037–0.249

On Adult the three cheaper attacks reach AUC 0.483 [0.459, 0.508], 0.498 [0.473, 0.524] and 0.500 against CoRTeC's 1,800 records, and 0.613, 0.616 and 0.625 against the leaking control, with 249 member matches and no non-member match. The per-record attack reaches AUC 0.497 against CoRTeC on the clinical data (advantage 0.006) and 0.595 against the control (advantage 0.191). The largest advantage in Table 25 is 0.048, against a bound of 0.762 (0.051 at $\epsilon = 8$ in the budget sweep below), and no synthetic record in any dataset exactly matches any private record. The positive control separates on every dataset, so the nulls are properties of the output rather than of blind attacks.

Across budgets the measured advantage stays flat where the bound grows: 0.031, 0.047, 0.028 and 0.051 at $\epsilon = 0.3, 1, 2$ and 8 against permitted advantages of 0.149, 0.462, 0.762 and 0.999. Every attack AUC's interval contains chance (Table 25; technical report, Section 7.8). We report the low false-positive regime as well, following Carlini et al. [8],

because an average-case summary can hide an attack that is confidently right about a few individuals. The true-positive rate at 0.1% false positives is at or below 0.002 on every dataset in Table 25, against 0.037 to 0.249 on the controls, and 0.004 on the shipped draws (Appendix C.3).

The shipped draws. Table 25 attacks the earlier-configuration arms. We re-ran the four attacks on the three shipped-configuration Adult draws of Table 3, 900 records, at three independent candidate samples of 1,000 and one of 3,000 (Appendix C.3). The strongest advantage on any attack and any sample is 0.049; at 3,000 candidates it is 0.034. None of the twelve attack-and-sample combinations at 1,000 candidates has an interval that excludes chance. One tendency is consistent: the nearest-neighbour statistic reads at or below chance, between 0.476 and 0.502 at 1,000 candidates and 0.483 [0.469, 0.498] at 3,000; its interval at 3,000 candidates is below chance by 0.002, as it did on the earlier arm (0.483) and on the earlier release of the same configuration (0.463 to 0.493). Below chance means the private records lie slightly farther from the synthetic rows than held-out records do, the opposite of memorisation. The same attack on MST’s and AIM’s output from the same training split reads 0.485 [0.470, 0.499] and 0.485 [0.471, 0.500], so the tendency belongs to the split and the statistic and not to CoRTeC; an adversary who flips the score gains an advantage of at most 0.034 on any of the three, under a twentieth of the permitted 0.762. No synthetic record matches a private record. At its operating point the shadow-model attack on the shipped draws records accuracy 0.513 against a 50% base rate, F1 0.513 and a true-positive rate of 0.004 at 0.1% false positives, against 0.581, 0.161 Youden’s J and 0.037 on the leaking control (technical report, Appendix C).

6.11 Cost

Table 26: Computational and monetary cost. Generation costs are measured from the token counts each vendor reported over our own runs, priced at list rates. Rates on 8 October 2026: Gemini 3.5 Flash \$1.50 and \$9.00 per million input and output tokens, reasoning tokens billed as output; Claude Fable 5 \$10 and \$50; Gemini 3.1 Pro \$2 and \$12; GPT-5 \$1.25 and \$10. An earlier build priced Gemini 3.5 Flash at the 2.5 Flash rate, 3.6 times lower on output, and its Gemini figures were low by that factor; the figures here are corrected. They are indicative rather than a benchmark. They exclude the reasoning-suppressed configurations of Section 6.6, whose apparent cheapness is not a saving.

method	fit cost	per-record generation cost	scaling
MST	23–135 s	free after fit	stable across our datasets
AIM	23–44 min (Adult); 58 s (NHANES); 16–29 min (finance, 12 columns); over 3 h without completing (Diabetes 130; finance on 15 columns)	free after fit	governed jointly by attributes and rows
PATE-CTGAN	42–65 min	free after fit	stable
DP-CTGAN	2.2 h (Adult)	free after fit	
CoRTeC, shipped configuration (Gemini 3.5 Flash)	seconds (the release)	\$5.2–8.4 per 1,000 generated rows; $\times 2$ –3 for the pool, \$15–25 per 1,000 kept records	linear in records requested
CoRTeC without the pool (Gemini 3.5 Flash / Claude Fable 5 / Gemini 3.1 Pro / GPT-5)	seconds	\$3.7 / \$4.84 / \$5.21 / \$9.36 per 1,000 records	linear

The asymmetry runs both ways. AIM’s and MST’s cost is one-off, and then sampling is free, which is decisive at the scale of millions of records. CoRTeC’s release takes seconds, its generation is trivially parallel and resumable, and it does not constrain where the compute runs. AIM’s fit did not complete within three hours on the hospital dataset or on the full finance schema. The exact-count prompt roughly doubles the reasoning tokens a call spends, and the pool multiplies the rows generated per row kept. The nine shipped-configuration draws of Section 6.1 cost about \$55 in all at the corrected rates: \$8.7 on NHANES, \$24 on Adult and \$22.7 on finance.

The cheapest generator we measured is not the weakest. On the hospital data Gemini 3.5 Flash matches Claude Fable 5’s conditional error (0.010 against 0.009) with the lowest 1-way error of any CoRTeC configuration (0.035), at three quarters of Claude Fable 5’s cost. It spends more reasoning per call than the Pro tier, which is consistent with Section 6.6. What the method needs is a reasoning-capable generator, not an expensive one.

7. Deployment Architecture

This section is written for the team that has to build, review and operate the system. It states where the trust boundary sits, what crosses it, and what the alternatives require. The reference architecture is drawn in the technical report (Figure 2): only one arrow crosses the trust boundary, and it carries R .

R is a differentially private release, and publishing it is what differential privacy was designed to make safe. Everything below the boundary is post-processing, so it can be repeated without limit, run by a different team, or re-run a year later, at no additional privacy cost.

Trust zone 2 is the enterprise surface, not a public API endpoint. The weights are the same either way, and CoRTeC's privacy argument holds against a hostile endpoint by construction, since the request carries only R . What does not hold is the compliance argument, which rests on tenant isolation, private networking, data residency and a business associate agreement. Our capability results are properties of the model weights and the prompt, and the same weights are served on both surfaces. We tested that on NHANES with one release, one model and $n = 600$, three draws through the public developer API and three through Vertex AI. No metric separates the two surfaces: the largest gap is 0.006 on 2-way total variation ($p = 0.12$), and every downstream gap is at most 0.009 AUC ($p \geq 0.44$). The contractual properties were never exercised by our runs and are the deploying institution's to verify.

Controls. The release artefact carries the parameters a reviewer needs, following NIST SP 800-226 [33] and SP 800-188 [32]: the variant (pure ϵ , central, $\delta = 0$), the add/remove neighbouring relation, the privacy unit, and the composition rule and ϵ of every query. A privacy ledger is the sole source of noise scales and seals after release. A property test releases at five seeds and requires every numeric leaf of the release to move unless it is an allowlisted public quantity. That is the check that catches an undeclared query, which a ledger summing declared queries cannot (Section 9).

The measured re-identification evidence of Section 6.10 is zero exact matches on four datasets and four attacks validated on a positive control. That is the kind of evidence the de-identification frameworks ISO/IEC 27559 [23] and ISO/IEC 20889 [22], Article 25 of the GDPR [16] and the HIPAA Expert Determination route [47], which requires a statistical assessment of re-identification risk, ask for; we claim conformance with none of them (technical report, H.6.1). The utility transmission bound of Stage C (Section 4.6) is deliberately excluded from that row. It bounds how much conditional structure survived generation, a utility quantity, and mapping it to a re-identification standard would be a category error with compliance consequences. The reference implementation's bound report names the standards it does not claim, with the reason for each.

Operational failure modes. Every guardrail in the reference implementation corresponds to a failure observed in this project before it was guarded: a tool that re-released whenever its output directory was new and spent the budget twice (now a hash check before every run), a release that published exact cohort sizes beside correctly noised rates and passed a ledger audit (now the five-seed property test above), and the cell-wise and pool-coverage failures of Sections 6.8 and 4.5 (now refused). Section 9 discusses the ones that touched the guarantee; the technical report's Appendix G tabulates all of them with the test that now carries each defect's name.

8. Discussion

8.1 Choosing among the mechanisms

The evidence supports a selection rule stated by deliverable rather than by method.

If the deliverable is a model trained on the synthetic data, CoRTeC has the largest measured advantage on this deliverable among the mechanisms we ran. No student separates from the real-sample floor on Adult or finance; on NHANES the random forest is 0.049 short and the other two students within 0.036. Models trained on AIM's and MST's output are 0.02 to 0.18 AUC lower, and 0.15 to 0.18 lower on Adult after correction. On Adult that margin is over the library defaults and does not survive tuning: AIM with a larger model or a 3-way workload trains the tree students at the floor and the linear student 0.03 short, at 30 minutes and 13.4 hours of fitting (Section 6.1). The claim is the narrower one, that CoRTeC reaches the floor with no fitting, and Section 8.2 shows that most of the default margin is attributable to what is released.

If the deliverable is a marginal report, a contingency table or a published set of cross-tabulations, the answer depends on scale. At $n = 300$ CoRTeC’s 1-way error is within 0.005 of MST’s on Adult and finance, below it on NHANES, and below AIM’s on every dataset. At adequate n AIM records the lowest error on its own 3-way workloads, and both marginal methods sample any number of records at no cost once fitted. For a marginal report at scale, use them.

If the deliverable is a calibrated conditional rate, a readmission probability for a patient group or a default rate for a credit segment, note that it is the conditional measures rather than the marginal ones that track downstream utility ($r = -0.64$ to -0.70 against $|r| \leq 0.16$). On this axis the marginal methods’ error is furthest from the real sample’s, while their 1-way error is closest to it. A procurement decision made on 1-way total variation alone will therefore select against this deliverable.

If the constraint is scale, the marginal methods pay their cost once and then sample freely, where CoRTeC pays per record, three times over under the shipped configuration. At millions of records that favours them regardless of the utility gap.

If the constraint is that no private data may leave the institution, CoRTeC transmits a release and never a record, so the constraint is satisfied by construction even when the generator is a frontier model reached through the institution’s own tenant-isolated endpoint. DP-SGD and PATE methods place the private data on the training hardware and so constrain where they run.

If the data is small, check the release before generating. Its noise-to-signal ratio and its cell count are computable from the release at no cost, and Section 6.5 shows they say whether conditioning can contribute at all.

8.2 A hybrid for institutions that will not run a language model

Relabelling a marginal method’s output using a private conditional table is pure post-processing of two already-private artefacts, so it costs nothing beyond the table. Table 28 measures it on Adult, five base draws per method crossed with three table draws for AIM and two for MST, under the same evaluator. Each private table is released at $\epsilon = 0.333$, split equally across the levels it carries, on top of the base method’s $\epsilon = 2$, so every hybrid row is at $\epsilon = 2.333$ per row. Relabelling moves AIM from TSTR-LR 0.675 to 0.777 and MST from 0.690 to 0.773. At level 4 the private table matches a non-private oracle to within 0.009, so the residual is draw-to-draw noise rather than a cost paid for privacy.

Richness is necessary. A level-2 table fixes calibration and adds little utility, and the large gain arrives only with the richer table. Richer is not monotonic, since level 6 is worse than level 4 on every student for both base methods. This is also the strongest available answer to the objection that the marginal methods are merely under-tuned: the gap is largely attributable to what each mechanism releases, and a practitioner who wants the conditional structure can obtain much of it by augmenting the marginal method.

Assignment is by an exact per-cell count with stochastic rounding over a random permutation of the cell. A rank-preserving assignment, our original default, was measured to be worse on three datasets at three seeds each (independent assignment within a cell scored higher in 9 of 9 runs). The guard meant to enable ranking scored the synthesiser’s self-consistency rather than its validity, and so selected for the failure it was built to prevent.

The hybrid ships as the second reference implementation ([cortec-hybrid](#)). It reports whether the correction helped and tells the user to keep their budget when it did not. Across eleven datasets the correction improves conditional calibration almost everywhere while moving downstream AUC in both directions.

Table 28: The hybrid on Adult. Giving AIM and MST the quantity neither releases removes most of the gap to CoRTeC without altering either synthesiser’s configuration.

condition	1-way TV ↓	cond. seen ↓	TSTR-LR ↑	TSTR-RF ↑	TSTR-GBM ↑
AIM alone	0.037	0.054	0.675	0.700	0.691
AIM + private conditional table, level 2	0.037	0.014	0.700	0.726	0.680
AIM + private conditional table, level 4	0.038	0.054	0.777	0.840	0.810
AIM + level 4, non-private oracle table	0.039	0.053	0.786	0.841	0.810
AIM + level 6	0.038	0.071	0.742	0.778	0.735
MST alone	0.024	0.169	0.690	0.728	0.681
MST + level 2	0.025	0.053	0.727	0.737	0.695

condition	1-way TV ↓	cond. seen ↓	TSTR-LR ↑	TSTR-RF ↑	TSTR-GBM ↑
MST + level 4	0.025	0.094	0.773	0.838	0.807
MST + level 4, non-private oracle table	0.025	0.096	0.780	0.843	0.815
MST + level 6	0.025	0.118	0.717	0.757	0.716

9. Threats to Validity: Measurement Artefacts

Defects arose throughout this work, and every one of them produced a plausible but wrong scientific conclusion before it was caught. We report them because we believe the field under-reports them, and because each is a trap for any group building a comparable pipeline. The technical report tabulates twenty-eight that bear on measurement and privacy accounting. The ones a reader should weigh are these.

The instruments, not the results. A released quantity that carries no noise is invisible to a budget audit built by instrumenting the noise mechanism. Our research pipeline published per-cohort record counts exact for most of the project while the audit reported a clean ϵ throughout, because the audit summed the queries it could see. The shipped tool had earlier been caught publishing exact cohort sizes and per-cell supports beside correctly noised rates, a real violation, again with a clean ledger.

The corrected check is behavioural rather than structural: re-release the same data at several seeds and require that every published quantity moves unless it is explicitly public. It found the exact counts immediately, together with a rule that had been deleting rare categories from releases and, with them, real subpopulations (`race = Amer-Indian-Eskimo` from a census cohort, `race_ethnicity = other_multi` from a health-survey cohort). Neither changed a reported fidelity or utility number, because the counts were accurate and the categories were rare. Both changed what the release was entitled to claim about itself, which is the more serious kind of error. A verifier that sums declared queries cannot detect an undeclared one.

A saturated metric. The original primary metric of this project scored the real-data ceiling and the unconditioned baseline identically, and a verdict had been drawn from it before anyone compared the two. Checking every metric’s floor against its ceiling before trusting it caught that defect, and later a released standard deviation of 693.80 on an attribute whose range is a few decades. It produced Section 6.3.

The defect with a named victim. Every other entry corrupts a number. Cell-wise generation removed people (Section 6.8). The synthetic dataset was internally consistent, passed its fidelity checks and trained models to within one point of the alternative, and it contained no Asian, Mexican-American, other-Hispanic or multiracial records at all. Nothing in our own evaluation suite flagged it, including the conditional criterion this paper advances, because conditional error is computed over released cells, and those were the cells that were present.

Three more belong here. Telemetry needs the same floor-and-ceiling check as a metric: two claims about whether a model’s reasoning fired rested on a token count that was absent rather than zero, and were withdrawn once the reasoning block itself became the evidence. A repaired defect returned through a dependency upgrade that changed how a missing value renders, and surfaced only when a published table was re-run in a second environment and one baseline moved from 0.019 to 0.110; a separate loader defect mislabelled 135 NHANES respondents because `NaN ≥ 6.5` is false. And the evaluator’s right-closed bins differ from the release’s left-closed ones on edge integers (Section 5.3), by 0.003 on Adult’s 1-way error, with method ordering unchanged. The technical report’s Appendix I has all twenty-eight.

Four practices caught these, and we recommend all four.

- Check every metric’s floor against its ceiling before trusting it.
- Report several student models. This caught a hybrid result that reversed sign between linear and tree students.
- Inspect raw responses before concluding a backend is incapable. A truncated prompt, an output budget consumed by hidden reasoning and a mis-set effort parameter are indistinguishable from a negative result at the level of summary statistics.
- Check that a check can fail. Three separate verifications in this project gave false assurance: a ledger that summed only declared queries, an acceptance check whose name promised more than its assertion delivered, and a test module that had never run because of an import error.

10. Limitations

1. **The head-to-head is at $n = 300$ under one generator family.** The shipped configuration is measured with Gemini 3.5 Flash at three draws per dataset. On NHANES the same release was decoded by three generators under the per-outcome prompt (Table 34): Gemini 3.5 Flash, the open-weight gpt-oss-120b at low reasoning and GPT-5 at medium reasoning (three draws); no measure separates them after Holm correction at three draws, and the point differences that remain (random forest 0.637 under gpt-oss against 0.678 under Gemini) are below what three draws resolve. The Gemini arm under that prompt reproduces the shipped NHANES row to within 0.019 on every measure. The cross-vendor check through Claude Opus 5 is one complete pool on Adult, and the powered six-draw equivalence test was run with Claude Fable 5 on the earlier release design. GPT-5 at minimal reasoning reproduces the finance result at three draws and the NHANES utility result at three draws, with conditional fidelity behind Gemini’s (Appendix F). The inversion test and the Adult transmission sweep were repeated on GPT-5 under the current release path, which implements the pure- ϵ mechanism (Sections 6.3 and 6.4). The replication list, in order, is now: the shipped Adult and finance arms under the per-outcome prompt and under a second generator; three reasoning-on draws of GPT-5 on finance; and the remaining earlier-configuration arms under the current release path. At $n = 1,000$ on Adult the point estimates favour the real sample, and we state the equivalence claim at the size where it was demonstrated with adequate power.
2. **AIM enters the finance comparison only on a reduced schema and is absent from the hospital data.** Its fit exceeded three hours on the full 15-column finance schema and on Diabetes 130, against its own paper’s 24-hour allowance. The cause is localised to the six high-cardinality amount columns. On NHANES it completes in under a minute, and Table 5 reports it there.
3. **On NHANES the students and 2-way error do not reach the floor.** The random forest trains 0.049 short ($p = 0.033$), gradient boosting 0.036 ($p = 0.10$) and logistic regression 0.035 ($p = 0.32$), and 2-way error is 0.120 against the sample’s 0.081. The remaining linear gap lies in the one cohort whose diabetic class does not clear $n_{\min}$, where the output follows the generator’s placement below bin resolution rather than the release’s. Finer public bins where cohort sizes support them would leave the generator less room; sizing them is an auto-configuration rule we have not built.
4. **The $n_{\min}$ decisions behind the earlier releases read exact counts.** Algorithm 1 now makes every such decision from a noised, charged count, and Theorem 1 covers it. The releases behind the CoRTeC rows of Tables 3 to 6 were regenerated under that rule; the earlier releases, which compared exact counts with $n_{\min}$ as the marginal-synthesis literature does, remain behind the earlier-configuration arms, the second-vendor arms at minimal reasoning, the equivalence test, the 3-way workload table (technical report, Section 7.3) and the tuning comparison of Appendix G. The noisy threshold reproduces the earlier releases’ gate decisions with probability 0.26 on Adult, 0.24 on finance and 0.70 on NHANES, and Section 4.7 names the decisions that differ. The earlier-configuration arms additionally carry the (ϵ_L, δ) guarantee of Section 4.7 rather than pure ϵ ; the release path that produced them now implements the pure- ϵ mechanism, and re-running them is on the replication list of item 1.
5. **ϵ protects a row.** On encounter-level data with repeated individuals the per-person guarantee is weaker by the maximum contribution count, 40 on Diabetes 130. The auto-configurator has no concept of a person; on that dataset it selected `number_inpatient`, a proxy for how many rows a patient contributes. MST, compared against us at row-level ϵ on the same data, inherits the same per-person figure. The mitigation is the contribution cap of Section 3, taken before the release.
6. **Every real dataset is a public benchmark the generator has very likely seen.** The constructed registry of Section 6.3 rules out gross recitation and shows CoRTeC’s margin over an ungrounded model unchanged when the prior is removed. It does not rule out recall of the marginal distributions. An institutional extract, or a model of known training provenance, remains the experiment we have not run. Section 5.6 states these controls before the results, and Appendix E reports the open-weight control.
7. **The membership-inference result is bounded by the attacks we ran.** An absence of detectable leakage under four attacks validated on a positive control is not an absence of leakage. The attacks of Table 25 read earlier-configuration draws; Section 6.10 reports the same attacks on the shipped Adult draws. Adversaries stronger than these are excluded by the ϵ guarantee, not by our measurement.
8. **The transmission sweeps are single-seed on the clinical datasets.** Each perturbs one relationship at three interior points, so the curve shape between endpoints rests on one measurement per model.

9. **Quality is bounded by the generator and by its configuration.** A single flag moved conditional error 3.8×, and the flag must be verified from the vendor’s reported reasoning evidence rather than from a setting. Open-weight models we measured as controls did not reach the frontier band, which is why the deployment proposal names enterprise platforms.
10. **The coverage guard is a heuristic.** Its 90% floor lies in a five-point gap between the highest failing and lowest passing measurements. It answers which bands were released and not what is inside one. When a private conditional table can be conveyed to a language model without silent loss is open.
11. **Per-record cost** is decisive against CoRTeC at the scale of millions of records, and the shipped configuration generates three rows for every one it keeps.

11. Conclusion

The question a practitioner asks of synthetic data is simple: if I train on this instead of on the real thing, how much accuracy do I lose? For CoRTeC at $\epsilon = 2$ and $n = 300$ on three datasets, the answer is nothing that any student can detect on Adult or finance, and at most 0.049 AUC on NHANES, where the random forest is the one student that separates at three draws. The two marginal mechanisms in deployment today, measured on this deliverable, lose 0.02 to 0.18 AUC over the same data at their library defaults; on Adult, AIM given a larger model or a 3-way workload and hours to fit reaches the floor too. CoRTeC’s own marginal error is within 0.005 of the most accurate of them on Adult and finance and below it on NHANES, below a real sample of the same size on all three, at the release’s own distance from the private data.

The mechanism trains nothing. It spends the budget once, on cohort-conditioned histograms per outcome class and a conditional table over a disjoint partition, where parallel composition makes conditional structure cheap. It lets a frozen language model decode the release under exact counts, selection and a sub-bin rule, which together reach the release’s own fidelity at no privacy cost. Because only the release crosses the trust boundary, the generator can be a tenant-isolated enterprise endpoint, and the choice of model becomes a quality decision rather than a compliance one.

Two of the findings reach beyond the mechanism. Both criteria the field selects synthesisers on are saturated. Real data with its target permuted passes a 90% marginal-similarity bar, and on a public benchmark an ungrounded language model with no access to the private data comes within 0.010 of a real sample and exceeds the deployed mechanisms on aggregate downstream utility. Yet it is wrong about 72% of the subgroup where the institution’s data departs from public knowledge, and it reports a 98.5% readmission rate for a group whose true rate is 21.4%. Only conditional and subgroup measures, reported against a real-sample floor and a no-information floor, separate a mechanism that transmits an institution’s conditional structure from one that reproduces what was already public.

And whether a private relationship survives synthesis is a property of the mechanism family, not of the guarantee. MST carries a forced two-way relationship as faithfully as CoRTeC does and, on the one dataset where both measurements exist, still trains a tree student 0.082 AUC below a real sample’s; on Adult what it loses is measurable as a 2.8× inflation of pairwise feature dependence.

Where CoRTeC belongs is narrow and useful. It is the mechanism to use when a downstream model or a calibrated conditional rate is the product, and not the mechanism to use when a marginal report at scale is.

Ethics Statement

This work uses public benchmark datasets and a national health survey that is released for research. No private institutional data was used. The membership-inference attacks were run against synthetic data we generated from those benchmarks, with the positive controls constructed from the same public records. The mechanism is intended to reduce the privacy risk of sharing tabular data, and we have tried to state its guarantee and its limits precisely. The row-level privacy unit, the uncharged suppression decisions behind the earlier-release arms, the pretraining corpus outside the guarantee, and the difference between a utility bound and a privacy audit are each stated where they arise. A reader who takes any of them for more than it is would be worse protected than they believe.

Reproducibility Statement

Two repositories accompany this paper. The research repository ([Calyie/cortec](#)) holds the pipeline that produced every table, the figure and build scripts, and the companion [technical report](#). The per-draw result records every published number is re-derived from, and the audit suite that re-derives them, are retained in the project’s internal tree and are available from the authors on request. The audit suite has four scripts. One recomputes every headline number from the stored records. One asserts that the paper and the shipped tools agree on every parameter and rule. One scans the code for the defect patterns of Section 9. One checks that every number in this paper appears in the technical report.

The tools repository ([Calyie/cortec-framework](#)) holds the two Apache-2.0 reference implementations with a test suite in which every regression test is named after the defect it prevents. The technical report’s Appendix A gives the environment, the commands and the spend. Released statistics cannot be regenerated bit for bit, because the noise source is cryptographically secure and ignores any seed; every stored release is therefore kept, and every draw reuses it by file.

References

- [1] Martín Abadi, Andy Chu, Ian Goodfellow, H. Brendan McMahan, Ilya Mironov, Kunal Talwar, and Li Zhang. Deep learning with differential privacy. In *ACM SIGSAC Conference on Computer and Communications Security (CCS)*, pp. 308–318, 2016.
- [2] Michael Aerni, Javier Rando, Edoardo Debenedetti, Nicholas Carlini, Daphne Ippolito, and Florian Tramèr. Measuring non-adversarial reproduction of training data in large language models. In *International Conference on Learning Representations (ICLR)*, 2025.
- [3] Tejumade Afonja, Hui-Po Wang, Raouf Kerkouche, and Mario Fritz. DP-2Stage: Adapting language models as differentially private tabular data generators. *Transactions on Machine Learning Research*, 2025.
- [4] American Diabetes Association. Classification and diagnosis of diabetes: Standards of medical care in diabetes, 2017. *Diabetes Care*, 40(Supplement 1):S11–S24, 2017.
- [5] Vadim Borisov, Kathrin Seßler, Tobias Leemann, Martin Pawelczyk, and Gjergji Kasneci. Language models are realistic tabular data generators. In *International Conference on Learning Representations (ICLR)*, 2023.
- [6] Mark Bun and Thomas Steinke. Concentrated differential privacy: Simplifications, extensions, and lower bounds. In *Theory of Cryptography Conference (TCC)*, pp. 635–658, 2016.
- [7] Kuntai Cai, Xiaoyu Lei, Jianxin Wei, and Xiaokui Xiao. Data synthesis via differentially private Markov random fields. *Proceedings of the VLDB Endowment*, 14(11):2190–2202, 2021.
- [8] Nicholas Carlini, Steve Chien, Milad Nasr, Shuang Song, Andreas Terzis, and Florian Tramèr. Membership inference attacks from first principles. In *IEEE Symposium on Security and Privacy*, pp. 1897–1914, 2022.
- [9] CDC/NCHS. National Health and Nutrition Examination Survey (NHANES) 2017–2018 data files. Centers for Disease Control and Prevention, National Center for Health Statistics, 2020.
- [10] Kai Chen, Xiaochen Li, Chen Gong, Ryan McKenna, and Tianhao Wang. Benchmarking differentially private tabular data synthesis. *arXiv preprint arXiv:2504.14061*, 2025.
- [11] W. Edwards Deming and Frederick F. Stephan. On a least squares adjustment of a sampled frequency table when the expected marginal totals are known. *Annals of Mathematical Statistics*, 11(4):427–444, 1940.
- [12] Dheeru Dua and Casey Graff. UCI machine learning repository. University of California, Irvine, School of Information and Computer Sciences, 2019.
- [13] Cynthia Dwork, Frank McSherry, Kobbi Nissim, and Adam Smith. Calibrating noise to sensitivity in private data analysis. In *Theory of Cryptography Conference (TCC)*, pp. 265–284, 2006.
- [14] Cynthia Dwork and Aaron Roth. The algorithmic foundations of differential privacy. *Foundations and Trends in Theoretical Computer Science*, 9(3–4):211–407, 2014.
- [15] Cynthia Dwork, Guy N. Rothblum, and Salil Vadhan. Boosting and differential privacy. In *IEEE Symposium on Foundations of Computer Science (FOCS)*, pp. 51–60, 2010.

- [16] European Union. Regulation (EU) 2016/679 of the European Parliament and of the Council (General Data Protection Regulation), Article 25 and Recital 26. *Official Journal of the European Union*, 2016.
- [17] Georgi Ganev, Bristena Oprisanu, and Emiliano De Cristofaro. Robin Hood and Matthew effects: Differential privacy has disparate impact on synthetic data. In *International Conference on Machine Learning (ICML)*, pp. 6944–6959, 2022.
- [18] Georgi Ganev, Meenatchi Sundaram Muthu Selva Annamalai, and Bogdan Kulynych. Tight auditing of differential privacy in MST and AIM. In *Theory and Practice of Differential Privacy (TPDP)*, 2026. arXiv:2604.18352.
- [19] Michael Hay, Ashwin Machanavajjhala, Gerome Miklau, Yan Chen, and Dan Zhang. Principled evaluation of differentially private algorithms using DPBench. In *ACM SIGMOD International Conference on Management of Data*, pp. 139–154, 2016.
- [20] Sture Holm. A simple sequentially rejective multiple test procedure. *Scandinavian Journal of Statistics*, 6(2):65–70, 1979.
- [21] Naoise Holohan, Stefano Braghin, Pól Mac Aonghusa, and Killian Levacher. Diffprivlib: The IBM differential privacy library. *arXiv preprint arXiv:1907.02444*, 2019.
- [22] ISO. ISO/IEC 20889:2018, Privacy enhancing data de-identification terminology and classification of techniques. International Organization for Standardization, 2018.
- [23] ISO. ISO/IEC 27559:2022, Information security, cybersecurity and privacy protection: Privacy enhancing data de-identification framework. International Organization for Standardization, 2022.
- [24] James Jordon, Jinsung Yoon, and Mihaela van der Schaar. PATE-GAN: Generating synthetic data with differential privacy guarantees. In *International Conference on Learning Representations (ICLR)*, 2019.
- [25] Ron Kohavi. Scaling up the accuracy of naive-Bayes classifiers: A decision-tree hybrid. In *International Conference on Knowledge Discovery and Data Mining (KDD)*, pp. 202–207, 1996.
- [26] Zinan Lin, Sivakanth Gopi, Janardhan Kulkarni, Harsha Nori, and Sergey Yekhanin. Differentially private synthetic data via foundation model APIs 1: Images. In *International Conference on Learning Representations (ICLR)*, 2024.
- [27] Ryan McKenna, Daniel Sheldon, and Gerome Miklau. Graphical-model based estimation and inference for differential privacy. In *International Conference on Machine Learning (ICML)*, pp. 4435–4444, 2019.
- [28] Ryan McKenna, Gerome Miklau, and Daniel Sheldon. Winning the NIST contest: A scalable and general approach to differentially private synthetic data. *Journal of Privacy and Confidentiality*, 11(3), 2021.
- [29] Ryan McKenna, Brett Mullins, Daniel Sheldon, and Gerome Miklau. AIM: An adaptive and iterative mechanism for differentially private synthetic data. *Proceedings of the VLDB Endowment*, 15(11):2599–2612, 2022.
- [30] Frank McSherry. Privacy integrated queries: An extensible platform for privacy-preserving data analysis. In *ACM SIGMOD International Conference on Management of Data*, pp. 19–30, 2009.
- [31] Ilya Mironov. On significance of the least significant bits for differential privacy. In *ACM Conference on Computer and Communications Security (CCS)*, pp. 650–661, 2012.
- [32] NIST. De-identifying government datasets: Techniques and governance. *NIST Special Publication 800-188*, Simson L. Garfinkel, Joseph Near, Aref N. Dajani, Phyllis Singer, and Barbara Guttman, National Institute of Standards and Technology, 2023.
- [33] NIST. Guidelines for evaluating differential privacy guarantees. *NIST Special Publication 800-226*, Joseph P. Near, David Darais, Naomi Lefkovitz, and Gary S. Howarth, National Institute of Standards and Technology, 2025.
- [34] OpenDP. SmartNoise Synth, version 1.0.8. <https://github.com/opendp/smartnoise-sdk>, 2024.
- [35] Nicolas Papernot, Martín Abadi, Úlfar Erlingsson, Ian Goodfellow, and Kunal Talwar. Semi-supervised knowledge transfer for deep learning from private training data. In *International Conference on Learning Representations (ICLR)*, 2017.
- [36] Nicolas Papernot, Shuang Song, Ilya Mironov, Ananth Raghunathan, Kunal Talwar, and Úlfar Erlingsson. Scalable private learning with PATE. In *International Conference on Learning Representations (ICLR)*, 2018.

- [37] Diane Ridgeway, Mary F. Theofanos, Terese W. Manley, and Christine Task. Challenge design and lessons learned from the 2018 differential privacy challenges. *NIST Technical Note 2151*, 2021.
- [38] Lucas Rosenblatt, Xiaoyan Liu, Samira Pouyanfar, Eduardo de Leon, Anuj Desai, and Joshua Allen. Differentially private synthetic data: Applied evaluations and enhancements. *arXiv preprint arXiv:2011.05537*, 2020.
- [39] Nabeel Seedat, Nicolas Huynh, Boris van Breugel, and Mihaela van der Schaar. Curated LLM: Synergy of LLMs and data curation for tabular augmentation in low-data regimes. In *International Conference on Machine Learning (ICML)*, 2024.
- [40] Reza Shokri, Marco Stronati, Congzheng Song, and Vitaly Shmatikov. Membership inference attacks against machine learning models. In *IEEE Symposium on Security and Privacy*, pp. 3–18, 2017.
- [41] Theresa Stadler, Bristena Oprisanu, and Carmela Troncoso. Synthetic data: Anonymisation groundhog day. In *USENIX Security Symposium*, pp. 1451–1468, 2022.
- [42] Beata Strack, Jonathan P. DeShazo, Chris Gennings, Juan L. Olmo, Sebastian Ventura, Krzysztof J. Cios, and John N. Clore. Impact of HbA1c measurement on hospital readmission rates: Analysis of 70,000 clinical database patient records. *BioMed Research International*, 2014:781670, 2014.
- [43] Marika Swanberg, Ryan McKenna, Edo Roth, Albert Cheu, and Peter Kairouz. Is API access to LLMs useful for generating private synthetic tabular data? *arXiv preprint arXiv:2502.06555*, 2025.
- [44] Yuchao Tao, Ryan McKenna, Michael Hay, Ashwin Machanavajjhala, and Gerome Miklau. Benchmarking differentially private synthetic data generation algorithms. *arXiv preprint arXiv:2112.09238*, 2021.
- [45] Toan V. Tran and Li Xiong. Differentially private tabular data synthesis using large language models. *arXiv preprint arXiv:2406.01457*, 2024.
- [46] Toan Tran, Arturs Backurs, Zinan Lin, Victor Reis, Li Xiong, and Sergey Yekhanin. Differentially private synthetic data via APIs 4: Tabular data. In *International Conference on Machine Learning (ICML)*, 2026. *arXiv:2606.08259*.
- [47] U.S. Department of Health and Human Services. Guidance regarding methods for de-identification of protected health information in accordance with the HIPAA Privacy Rule. Office for Civil Rights, 2012.
- [48] Chulin Xie, Zinan Lin, Arturs Backurs, Sivakanth Gopi, Da Yu, Huseyin A. Inan, Harsha Nori, Haotian Jiang, Huishuai Zhang, Yin Tat Lee, Bo Li, and Sergey Yekhanin. Differentially private synthetic data via foundation model APIs 2: Text. In *International Conference on Machine Learning (ICML)*, pp. 54531–54560, 2024.
- [49] Liyang Xie, Kaixiang Lin, Shu Wang, Fei Wang, and Jiayu Zhou. Differentially private generative adversarial network. *arXiv preprint arXiv:1802.06739*, 2018.
- [50] Lei Xu, Maria Skoularidou, Alfredo Cuesta-Infante, and Kalyan Veeramachaneni. Modeling tabular data using conditional GAN. In *Advances in Neural Information Processing Systems (NeurIPS)*, 2019.
- [51] I-Cheng Yeh and Che-hui Lien. The comparisons of data mining techniques for the predictive accuracy of probability of default of credit card clients. *Expert Systems with Applications*, 36(2):2473–2480, 2009.
- [52] Jun Zhang, Graham Cormode, Cecilia M. Procopiuc, Divesh Srivastava, and Xiaokui Xiao. PrivBayes: Private data release via Bayesian networks. *ACM Transactions on Database Systems*, 42(4):25:1–25:41, 2017.

Appendix A. The Prompt

The reference implementation freezes and fingerprints its templates, verifies the fingerprint before every render, and requires a user who needs a different template to register it under a new version. It does so because two elements are essential and their removal is not visible in the output: the pipeline still runs and still produces plausible rows, and is simply no longer conditioned on the data. The system message and the cohort template follow, with the exact-count block that Algorithm 3 fills.

```

1  SYSTEM
2  You generate synthetic tabular records for privacy research. You will be
3  given summary statistics that were computed under differential privacy.
4  Reproduce the distributions and relationships they describe as closely as
5  you can, EVEN IF THIS CONTRADICTS YOUR EXPECTATIONS about how these
6  variables usually relate. The statistics describe this specific
7  population; your general knowledge does not. Output only CSV rows. No
8  commentary, no explanation, no markdown fences.
9
10 USER
11 Generate exactly {n_rows} synthetic records for the following subgroup.
12
13 SUBGROUP: {cohort_name}
14
15 These statistics were measured on the real data for THIS subgroup, under
16 differential privacy. Match them. Where a statistic below conflicts with
17 what you would otherwise expect, follow the statistic: it is a
18 measurement of the actual population and your expectation is not.
19
20 NUMERIC DISTRIBUTIONS (released histograms; reproduce the shape, not just
21 the mean)
22 {numeric_block}
23
24 CATEGORICAL DISTRIBUTIONS (all released categories and their proportions)
25 {categorical_block}
26
27 OUTCOME RATE IN THIS SUBGROUP
28 {class_balance_block}
29
30 CONDITIONAL OUTCOME TABLE (P({target} = {positive} | cell), measured under
31 differential privacy)
32 This table is the most important part of this prompt. Each row states the
33 outcome rate for a specific cell of the population. Your generated records
34 must reproduce these rates, even where a rate is the opposite of what you
35 would expect for that group.
36 {conditional_block}
37
38 EXACT COUNTS FOR THIS BATCH (the number of rows, out of {n_rows}, that
39 must fall in each bin, each category and each outcome; these are the
40 counts this subgroup still owes)
41 {counts_block}
42
43 OUTPUT FORMAT
44 Exactly {n_rows} CSV data rows, plus one header row, with these columns in
45 this order:
46 {columns}
47
48 Rules:
49 - every numeric value must lie within its stated range
50 - {target} must be exactly "{positive}" or "{negative}"
51 - do not repeat identical rows; vary records the way real data varies
52 - output nothing except the header and the {n_rows} data rows

```

In a cohort with class-conditional blocks, the numeric and categorical blocks are given once per outcome class. The matched header-only control of Section 6.3 is this prompt with the five released blocks removed and nothing else changed; the plain header-only control gives the model only the column names. Every value in every block is a released quantity; the prompt never carries a private record.

Appendix C. Parameters, Artefact and Audits

This appendix carries what an implementer needs from the paper. The operational manual, with the full failure-mode catalogue, the deployment checklist with its rationale, the two deployment patterns, the surface adapters and the cost model, ships as [documentation in the tools repository](#).

C.1 Parameters. Table 29 lists the shipped defaults and what each was set from.

Table 29: Shipped parameters.

parameter	default	set from
ϵ_{total}	2.0	the budget every head-to-head in this paper runs at; on a large dataset the output is flat over [0.3, 8], on a small one it is not (Section 6.5)
conditional share α	0.2	a sweep of the release decoded with no model: a fifth costs no measurable conditional accuracy once the release carries class blocks, and the histograms' error falls by a third
count share γ	0.02 (research pipeline); in the tool 0.05 of the available budget plus min(0.05 of the available budget, 0.25 of the marginal share), half to cohort sizes and half to cell supports, the cell half divided across the declared levels	the published cohort sizes and cell supports are private counts, paid for out of the marginal share, and every $n_{\min}$ decision reads them
suppression floor $n_{\min}$	150	a conditional rate over fewer than about 50 records is dominated by its own Laplace noise; 150 leaves the class blocks estimable on cohorts of a few hundred; the tool refuses $n_{\min} < 50$
batch size B	25 rows	the largest batch on which the frontier models reproduce every count line exactly
pool factor k	3 (2 on NHANES)	the selection's gain saturates between 2 $\times$ and 3 $\times$; each further unit costs one generation spend
pool coverage floor	1.1 $\times$ the rows each cohort owes	the failed pool of Section 4.5
cell-wise coverage floor	90% of each conditioning column's released mass	placed between the highest failing measurement (0.858) and the lowest passing one (0.911) over eleven per-column measurements on two datasets
sub-bin rule	release (opt-out generator)	Table 10; technical report, H.17
reasoning	on	Table 19; suppressing it warns with the measured 3.8 $\times$ cost
Stage C tolerance τ	derived from the release: $\ln(k/\alpha)/(n_{\min} \epsilon_{\text{cert}}) + \frac{1}{2} \max_c$	$\rho_c - \bar{\rho}$
Stage C minimum synthetic rows per cell	20	below it a cell rate moves by a third on three rows and (4) has no sampling term; no verdict is issued

C.2 The release artefact. The release is a JSON document containing no private record; its noise is drawn with the Laplace mechanism of diffprivlib [21]. Per cohort it carries the published size, the class balance, and one histogram per attribute and per outcome class, or one pooled histogram where a class fell below $n_{\min}$. Per conditional level it carries each surviving cell's published positive count, size and rate. Its audit block records every query with its ϵ , sensitivity, composition rule and partition key, and the totals: `epsilon_accounted` (per row), the privacy unit with `max_rows_per_person` and `epsilon_per_person`, the variant (pure ϵ , central, $\delta = 0$), and the neighbouring relation (add/remove). A `documented-gaps` block names the floating-point Laplace mechanism, the pretraining provenance of the generator and an undeclared privacy unit; it records that every $n_{\min}$ decision was a noisy threshold on a charged count, and names the uncharged suppression decisions only when `charge_suppression=False` was chosen.

The ledger seals after release, and any later attempt to spend raises. The artefact cannot be regenerated, because the noise source is cryptographically secure and ignores any seed. The stored artefact is therefore the only copy of that release, every draw must reuse it by file, and the generator verifies it by hash before every run. The guardrails enforced in code and the deployment checklist are in the technical report, Appendix G.2 and G.3.

C.3 Membership inference on the shipped draws. Table 32 reports the four attacks of Section 6.10 on the three shipped-configuration Adult draws (900 records), at three candidate samples of 1,000 and one of 3,000, with MST's and AIM's output from the same training split attacked the same way as a control on the nearest-neighbour statistic. Entries are attack AUC with a 95% bootstrap interval.

Table 32: Membership inference on the shipped Adult draws.

candidate sample	nearest neighbour	shadow model	per-record LiRA	exact matches	strongest advantage
1,000, seed 42	0.478 [0.453, 0.504]	0.508 [0.482, 0.533]	0.506 [0.481, 0.530]	0	0.045
1,000, seed 7	0.476 [0.450, 0.500]	0.516 [0.491, 0.542]	0.519 [0.496, 0.544]	0	0.049
1,000, seed 99	0.502 [0.476, 0.528]	0.506 [0.482, 0.531]	0.510 [0.485, 0.534]	0	0.020
3,000, seed 42	0.483 [0.469, 0.498]	0.493 [0.479, 0.508]	0.511 [0.497, 0.526]	0	0.034
<i>MST, 1,500 records, 3,000 candidates</i>	<i>0.485 [0.470, 0.499]</i>	<i>0.501 [0.486, 0.515]</i>	<i>0.495 [0.480, 0.510]</i>	<i>0</i>	<i>0.031</i>
<i>AIM, 1,500 records, 3,000 candidates</i>	<i>0.485 [0.471, 0.500]</i>	<i>0.509 [0.494, 0.523]</i>	<i>0.513 [0.497, 0.527]</i>	<i>0</i>	<i>0.030</i>
<i>positive control (leaking), 3,000 candidates, AUC</i>	<i>0.534</i>	<i>0.536</i>	<i>0.526</i>	<i>0.549</i>	

Appendix E. The Open-Weight Control

To establish that the mechanism is not a property of one vendor’s model, the Diabetes 130 transmission sweep of Section 6.4 was repeated on nine self-hosted open-weight models spanning six families and four scales, as scientific controls on the mechanism and not a deployment recommendation (Section 6.6); every row, the API reference row included, is the same `number_inpatient` sweep.

Table 33: Transmission of a planted relationship across model families. Mean absolute error is the quantity to read; slope is anchored by the endpoints and can read near unity while the midpoint is wrong by 0.3.

model	family	parameters	quantisation	slope	mean absolute error	midpoint error
Claude Fable 5 (API)	Anthropic	not public	none	0.995	0.009	+0.014
llama3.3:70b-instruct	Meta	70.6B	Q4_K_M	0.988	0.020	+0.040
qwen2.5:72b-instruct	Alibaba	72.7B	Q4_K_M	1.011	0.030	+0.079
mistral-small:24b-instruct	Mistral	23.6B	Q4_K_M	0.877	0.049	−0.013
gemma2:27b-instruct	Google	27.2B	Q4_K_M	0.890	0.067	+0.093
gpt-oss:20b	OpenAI	20.9B	MXFP4	0.913	0.078	+0.121
qwen2.5:32b-instruct	Alibaba	32.8B	Q4_K_M	1.014	0.098	+0.282
qwen2.5:14b-instruct	Alibaba	14.8B	Q4_K_M	1.011	0.105	+0.306
qwen2.5:7b-instruct	Alibaba	7.6B	Q4_K_M	0.208	0.406	−0.422

Every family tested at 20B parameters or above transmits the private relationship with a mean error of 0.10 or less. Every open-weight model is 4-bit quantised, so the table compares quantised weights and not released models, and gemma2’s 8,192-token training context, four times smaller than any other model’s, confounds its weaker score. Transmission fidelity is not generation fidelity: on full-dataset generation a self-hosted 70B model’s output is close to indistinguishable from an unconditioned prompt on the metrics this method exists to improve, which is why the deployment proposal names enterprise platforms.

Appendix F. The Second-Vendor Replication

Table 34: The shipped configuration generated through GPT-5 from the earlier release files of the Gemini arms, scored under the protocol of Section 5.3 beside the Gemini arms and the real-sample floor. The current-release rows are the arms of Tables 3 to 5, placed here for comparison; the GPT-5 arms were generated from the earlier release files, so they are read against the earlier-release rows. The minimal-reasoning arms are three draws; the low-reasoning NHANES arm is one draw from a pool that stopped at 572 of 600 rows at its spend cap and was selected offline.

condition	draws	1-way TV ↓	2-way TV ↓	cond. seen ↓	cond. held- out ↓	TSTR- LR ↑	TSTR- RF ↑	TSTR- GBM ↑
NHANES								

condition	draws	1-way TV ↓	2-way TV ↓	cond. seen ↓	cond. held- out ↓	TSTR- LR ↑	TSTR- RF ↑	TSTR- GBM ↑
CoRTeC (Gemini 3.5 Flash, reasoning on; current release)	3	0.016	0.120	0.013	0.036	0.738	0.679	0.681
CoRTeC (gpt-oss-120b, low reasoning; current release)	3	0.020	0.134	0.023	0.052	0.685	0.660	0.628
CoRTeC (Gemini 3.5 Flash, reasoning on; current release, counts per outcome)	3	0.017	0.128	0.014	0.032	0.733	0.678	0.662
CoRTeC (gpt-oss-120b, low reasoning; current release, counts per outcome)	3	0.019	0.137	0.027	0.028	0.716	0.637	0.643
CoRTeC (GPT-5, medium reasoning; current release, counts per outcome)	3	0.017	0.107	0.014	0.032	0.736	0.696	0.682
CoRTeC (Gemini 3.5 Flash, reasoning on; earlier release)	3	0.015	0.119	0.006	0.036	0.752	0.732	0.711
CoRTeC (GPT-5, minimal reasoning)	3	0.031	0.116	0.038	0.063	0.751	0.710	0.702
CoRTeC (GPT-5, low reasoning; one draw)	1	0.020	0.104	0.011	0.069	0.727	0.664	0.640
<i>real sample, n = 300</i>	3	0.034	0.081	0.015	0.036	0.773	0.728	0.716
finance								
CoRTeC (Gemini 3.5 Flash, reasoning on; current release)	3	0.029	0.123	0.016	0.028	0.689	0.721	0.699
CoRTeC (gpt-oss-120b, low reasoning; current release; one draw)	1	0.060	0.178	0.037	0.037	0.677	0.730	0.701
CoRTeC (GPT-5, medium reasoning; current release, counts per outcome; one draw)	1	0.028	0.120	0.019	0.022	0.697	0.735	0.713
CoRTeC (Gemini 3.5 Flash, reasoning on; earlier release)	3	0.029	0.125	0.014	0.022	0.680	0.731	0.712
CoRTeC (GPT-5, minimal reasoning)	3	0.033	0.125	0.019	0.026	0.683	0.711	0.703
<i>real sample, n = 300</i>	3	0.041	0.099	0.059	0.045	0.695	0.727	0.717
Adult								
CoRTeC (Gemini 3.5 Flash, reasoning on; current release)	3	0.026	0.106	0.017	0.040	0.839	0.875	0.844
<i>real sample, n = 300</i>	3	0.043	0.107	0.062	0.036	0.830	0.870	0.840

The comparisons the table supports are stated in Section 6.6; the Holm families are the fourteen-test families of Section 5.4.

Appendix G. The AIM Tuning Sweep

Table 35: AIM on Adult at $\varepsilon = 2$ and $n = 300$ under the smartnoise-synth defaults and under the two settings a practitioner would try first, fitted on the same training split under the same public bins and scored under the protocol of Section 5.3. Fit times are wall-clock on one four-core machine.

condition	draws	fit	1-way TV ↓	2-way TV ↓	cond. seen ↓	cond. held- out ↓	TSTR- LR ↑	TSTR- RF ↑	TSTR- GBM ↑
AIM, defaults (80 MB model, 2-way workload)	5	23 min	0.037	0.119	0.054	0.101	0.675	0.700	0.691
AIM, 300 MB model	3	30 min	0.034	0.107	0.045	0.029	0.772	0.867	0.835
AIM, 3-way workload	3	13.4 h	0.032	0.102	0.046	0.026	0.812	0.876	0.847
CoRTeC (Gemini 3.5 Flash), shipped configuration, earlier release	3	none	0.029	0.110	0.017	0.039	0.842	0.876	0.849
<i>real sample, n = 300</i>	3		0.043	0.107	0.062	0.036	0.830	0.870	0.840